

# $G_E^n$ Detection Equipment Status Report

---

**Brandon Craver**

**University of Virginia**


Hall A Collaboration Meeting

December 06, 2005

# What We Have Built


---

- Array of plastic scintillator counters.
- Veto plane provides proton rejection.
- Spatial resolution  $\sim 10$  cm.
- Time resolution  $\sim 0.3$  ns.
- Extract quasi-elastic events.
- Match BigBite's large momentum acceptance.



# What We Have Built


- Pre-Shower 2 x 27 Pb-Glass - Shielded PMTs.
- Main Shower 7 x 27 Pb-Glass - Shielded PMTs.
- Longitudinal Profile of the energy loss distinguishes electron from pion.
- Energy resolution 6-7%.
- Pion rejection factor  $> 100$ .
- Electron efficiency 0.97-0.98.



# What We Have Built

---


- **Three drift chambers:**
  - **1<sup>st</sup> and 3<sup>rd</sup> chambers**
    - Resolution  $\sim 200 \mu\text{m}$
  - **2<sup>nd</sup> chamber**
    - Resolution  $\sim 1\text{cm}$ : to increase high rate and multi-track capabilities
- **Active area:**
  - 1<sup>st</sup> 140 cm x 35 cm
  - 2<sup>nd</sup> and 3<sup>rd</sup> 200 x 50 cm



# Status of the Project


---

- **All chambers tested extensively:**
  - Hold HV well, very stable.
  - Dark current levels are very low.
  - No dead wires or noisy wires.
  - Parasitic high rate data taking during HAPPEX experiment
  - Efficiency and resolution studies completed on front chamber






# Cosmics Studies




# Studies with $^{55}\text{Fe}$ Source



# Source Studies - Efficiency


Efficiency of 1-X7, channel 3 - 9/7/05





# Source Studies - Resolution

Resolution vs. HV - 9/20



# Parasitic Beam Test

---

- Install chambers with no shielding at a distance of 10 m from the target and scattering angle  $\theta \sim 70^\circ$ .
- Luminosities in range  $1 * 10^{35} - 30 * 10^{35} \text{ cm}^{-2} \text{ Hz}$ .
- Chambers exhibit low current drain.
- High voltage is stable.
- Low energy background expected to be  $\sim 50 \text{ MHz}$  through front chamber.

# Milestones

---

- **November 1** – Completion of testing of BigBite. Completed November 28.
- **November 28** – Completion of N-arm testing in lab. Begin decabling. Passed – Decabling began November 29.
- **December 5** – Begin moving BigBite. Passed – Move scheduled for December 6.
- **January 5** – BigBite DAQ operational in hall.
- **January 16** – Install BigBite platform.
- **January 25** – N-arm DAQ operational in hall.
- **February 5** – Synchronized readout of full DAQ operational in hall.
- **February 9** - BigBite operational checkout.
- **February 22** - Neutron arm complete with shielding etc.