

He3 Target Lab Update

Yi Qiang, Duke University for C. Dutta/J. Katich/Y. Zhang/J. Huang

Transversity Collaboration Meeting

March 17, 2008





Since Last Collaboration Meeting

- ▶ A 3 inch cell (Gloucester) was placed in the oven.
- NMR was working w/o problem.
- ▶ EPR Finally worked.
- New oven pieces arrived. Still waiting for the tube.
- ▶ All 20 cells were made, waiting for characterization.
- Cell density measurement on its way (More details in Yi Zhang s talk).
- Design of Target flip signal on the way (More details in Jin Huang s talk).





3/17/2008



NMR Polarimetry

- ▶ 2 Lines of Lasers (29W each).
- Spin-up time: 8-9 hours.










EPR Polarimetry

- No EPR signal at the beginning.
- Problem was identified to be the insufficient EPR RF power:
 - Coil is far far away from the cell (10-15 cm compared to previous <5 cm);
 - Impedance mis-match introduced quite large power reflection;
 - Thin wire of coil brought low capacitance and lead no power dissipation in the inductance.







Increase EPR RF Power


- Put the coil inside the oven.
 - A first 10 turn coil was made of normal gauge magnetic wire (180C). Oven temperature was reduced to 170 C. Clean EPR signal was observed.
 - A second coil was made of high temperature magnetic wire (Gauge 250C) recently.
 Oven temperature was increased to 240 C.







EPR Setup




Fiber to Spectrometer





EPR Measurement

▶ Both **Rb** and **K** EPR line shapes can be seen at either 170 or 240 C.



65**Rb**

B=24.5G, Polarization~46%

³⁹K





More Work with EPR Coil

- ▶ Need a formal (permanent) design to put coil inside.
- High temperature aging test.
- A better impedance match (provide us stronger EPR RF signal with current pre-amplifiers). This work gets help from *John Musson*.





New Oven

- Pieces arrived last week. Joe is working on painting and assembling.
- ▶ 1/2 of the weight of current one (~20 lb.).
- New security features.
- Interior will be painted black to reduce reflections.
- ▶ EPR RF coil can be mounted inside with some modifications.
- 2 ovens will be made.





New Oven

- Oven pieces in process:
 - ▶ Red RTV first, then black spray.





10



Lasers and Optics Components

▶ FAP Lasers

- In lab and working: 5 Singles and 2 Duos;
- Being repaired: I Singles and I Duo (both by Coherent).

Long Optic Fibers

In the Hall.

Optic Component

- All parts are in lab now;
- Need to be tested;
- Three lines in total;
- Each component has at least 2 spares.



3/17/2008



Cells

12

- All 20 Cells have been made
 - ▶ 10 from W&M and 10 from UVA.
- ▶ I water cell is being filled in W&M.
- Target density measurement is under way.
- ▶ Other characterizations will start soon: density, polarization, spin-up/relaxation time, AFP loss...





Compass

- In the process of finishing up the determination of the "moment of inertia (MOI)" of the compass.
- Resolution verified to be 0.09 degrees.
- ▶ Plan to achieve 0.05 degrees.
- Customization to be done when it arrives at JLab.







| 13



Future Plan

- Our goal is to get ready to move into the Hall by the end of July, 2008.
- ▶ Before that, we need:
 - Water calibration: ~ I month;
 - Assembling new oven: ~ I month;
 - ▶ Cell characterizations: ~ 3 months;
 - ▶ EPR Coil test and final design: ~ I month;
 - ▶ Spin flip signal: ~ 2 month;
 - EPR lock-in tuning: ~ I month;
 - Optimization of Condition: ~ I month;
 - Software (Controlling, monitoring and AFP fail recovery): ~ 3 month;



Thank You!

