



EC and SPD Updates

The SoLID EC Working Group
SoLID Collaboration Meeting
September 11-12, 2015

Test Plan of May 2015 Collab Meeting

1. FMPMT high field test using FROST magnet (July) - done, but need to measure timing resolution in the lab
2. FASPD uniformity test with source (June → fine tuning groove design) - the source we tried was not strong enough. Will do a cosmic then beam test combined with GEM → fall 2015, more likely spring 2016
3. LASPD timing test with beam → fall 2015, more likely spring 2016.
4. More preshower prototype tests, including radiation resistance → fall 2015, more likely spring 2016.

Other Progress

1. Applied to EIC funding in hope of postdoc/student support, but was not funded this time.
2. Received production drawings of ALICE shashlyk modules from WSU, modified ours accordingly.
3. Prof. Feng (SDU) received funding enough to build 4 prototypes. Discussion at SDU/Hadron15 meeting. Procuring scintillator and lead pieces is underway.
4. Met ANL engineer on 9/10
 - ✦ discussed stress calculation of module assembly, under preload, actual load, and with modules cantilevered to the back support.
 - ✦ discussed support design, integration with module end plates.
 - ✦ initiated an email discussion with JLab engineers on solving the interference problem.

Prototype Design



Regular Hexgon: side length 62.5mm
 Material: 1.5mm ± 0.25mm Scintillator
 All units in mm

Four Quadrants Symmetric

- short discussion with Whit, concerned about stress on thread, but he will not have time until Sept.

- discussion with Iowa U. engineer: rods will sag under weight of module, suggested Al-wall design like ATLAS modules.

- but see next slide




SOLIDWORKS Student Edition.
 For Academic Use Only.

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS SURFACE FINISH TOLERANCES LENGTH ANGULAR		FINISH	DRILL AND BREAK SURF FINISH	DO NOT SCALE DRAWING	REVISION
DRAWN	NAME	SIGNATURE	DATE	TITLE	
CHK'D					
APP'VD					
WFG					
Q.A.					
MATERIAL:			DRAWING NO.		
WEIGHT			SCALE: 1:1		
			SHEET 1 OF 1		

SOLID EMCal Scintillator Plate


Module Load Calculation

500kg force to flatten layers; put in rods, turn nuts to snug; 78 lbf load on 6 rods after assembly plates are removed




Preloading on assembly stand

Turn nuts further so weight is completely balanced by static friction (642 lbf load on 6 rods, factor 2 included)



loading



Cantilevering add more stress to top 3 rods, 400 lbf alone on top rod (2 included)



Do not need support between preshower and shower ???

Module Support

From two years ago, will pick up again.



Pre R&D Need

- ✦ At least 1/2 postdoc to “develop an end-to-end realistic simulation and reconstruction to further optimize cost and physics reach and derive clear performance requirements for the individual subdetectors.”
- ✦ Resources to build 4 more prototype modules, PMTs and HVs, combine with the SDU prototypes and conduct in-beam test:
 - ◆ construction: \$34k material + (\$10k-\$20k) assembly stand, 1/4 postdoc, 1/2 tech or grad students, 3 summer undergrad.
 - ◆ testing: partial postdoc, 1/2 grad student
- ✦ Other items underway and covered by UVa
 - ✦ FASPD uniformity test
 - ✦ LASPD timing test with GEM
 - ✦ radiation resistance test
 - ✦ continue working with ANL engineers on module&support
 - ✦ continue working with JLab detector group on PMT base design&testing
 - ✦ misc: fiber, fiber connector,

Backup Slides

Shashlyk Production (IHEP)

- ▶ Mold: \$30k x 2 (scintillator), \$15k (lead); plus
- ▶ \$1270 per module, see below
- ▶ Same prototyping and mass production
- ▶ Not including 30% overhead

Component	Cost per module
Scintillator	\$200
Lead	\$240
flanges, nuts	\$230
assembly	\$320
add fiber mirror, testing	\$110

Prototyping (8 modules): \$55k+30%, plus fiber (\$2,961)

Mass production: \$2,361k + 30% = \$3,069k, plus fiber

Shashlyk Production (Alternate)

Component	3 modules	8 modules	1800 modules
scintillator (CHN#1)	\$10k	\$27k	\$1kx1800=\$1.8M
lead (Kolgashield)	\$7,776	\$17k	\$488k
paper (Kolgashield)	\$1,152	\$2.5k	\$130k
flanges, nuts, rods	\$600	\$1.6k	\$150x1800=\$270k
fiber mirror, testing	?		
Total w/o assembly	\$19.5k	\$48.1k	\$2,688k

fiber not included in table.

CHN: only #1 can do injection molding