

ECAL for GEp/SBS

B. Wojtsekhowski


Electron Calorimeter for GEp

Performance Requirements


- Function: Detect 4 to 5 GeV Electrons
- Energy resolution: $\sigma/E \sim 10\%$ for 3.5 GeV electrons
- Spatial resolution: 6-8 mm
(2 mm with upstream coordinate detector)
- Full luminosity: $8 \cdot 10^{38}$ Hz/cm²
- Trigger: Overlapping segments correlated with the proton Trigger at 75+% of elastic peak

BigCal for GEp experiment


Used in Hall C GEp3



Reconfigure




48+34+10 = 92 blocks



- **ECAL-SBS**
- Configuration: $(960 + 714 + 220) = 1894$ blocks 20-22 blocks
- Block size : $4.2 \times 4.2 \times 40$, $4 \times 4 \times 40$, and $3.8 \times 3.8 \times 45$ cm³
- Area: 0.84 m x $(2.02 + 1.36 + 0.38)$ m = 3.75 m²


BigCal for GEp experiment



The items to do for ECAL

1. Components

- i) Lead glass blocks
- ii) PMTs
- iii) HV bases
- iv) Front-end electronics
- v) Cables (signal and HV)
- vi) HV supplies
- vii) Fastbus system
- viii) NIM electronics



There are a lot of progress

2. Thermal annealing

- i) Measurement of the dark current
- ii) Irradiation of 8 blocks/ISU and more/RadCon
- iii) Optical bond technology
- iv) Mechanical stability at 275 C (eff. 250 hours)
- v) Annealing tests at 275, 250, 225, 200, 150 C
- vi) C16 project
- vii) Design of the 10% prototype (M200)
- viii) Budget of M200
- ix) Construction of M200
- x) M200 test in Hall A in the fall of 2014



The milestones for ECAL (4/16/2014)

1. July 2014: Develop concept of annealing, float is 2 months
 - i) Test
 - ii) Design
 - iii) Budget
2. May 2016: ECAL electronics is ready, float is 6 months
 - i) Inventory
 - ii) Design
 - iii) Construction
 - iv) Test
3. Sept. 2017: ECAL is ready for GEp run, float is 9 months
 - A) Design
 - B) Budget
 - C) Construction
 - D) Test

The milestones for ECAL 3/11/2015

1. July 2015: C16 resolution test, float is 4 months
 - i) Design 2/15/2015 – completed
 - ii) Construction 3/20/2015 – near completion
 - iii) Test 4/30/2015 – if beam available
2. May 2016: ECAL electronics is ready, float is 6 months
 - i) Inventory
 - ii) Design
 - iii) Construction
 - iv) Test
3. Sept. 2017: ECAL is ready for GEp run, float is 9 months
 - A) Design: stage 1 (C16 - BW); stage 2(C200 – SR); stage 3(ECAL-RW)
 - B) Budget: RW/MJ/BW
 - C) Construction: C200 at SBU in 2015-16; ECAL in JLab 2016-17
 - D) Test in TestLab

The milestones for ECAL 3/11/2015

1. July 2015: C16 resolution test, float is 4 months
 - i) Design 2/15/2015 – completed (BW)
 - ii) Construction 3/20/2015 – (BW)
 - a) heating regime - completed
 - b) detector signals -completed
 - c) cooling regime – under development
 - iii) Beam Test 4/30/2015 – (MJ)
 - a) platform at minimum angle
 - b) cables for HV, signals, T-sensors
 - c) Proton arm
 - d) DAQ/analysis

The milestones for ECAL 3/11/2015

- 2) May 2016: ECAL electronics is ready, float is 6 months
 - i) Inventory: Front End; Long Cables; DAQ; HV: DAQ crates/SFI/ADC/TDC/HV crates/HV units
 - i) Design:
 - ii) Construction: in progress
 - iii) Test: ADC readout test in progress