

# Coordinate Detector fabrication status

V.Baturin  
for Idaho State University  
18 May 2016


## **Fabrication**

- 168 Scintillator Blocks: finished.
- 168 Fiber Bundles : 58 (100% done) + 30 (75% done); plan-88.
- Diamond cutting machine needs new ball bearings.
- Module assembling: 1 module (50% done)

## **Quality assurance**


- Refraction on fiber channel and scintillator response.
- Fiber treatment and optical properties.
- Module assembling accuracy.

## Refraction and Fiber Acceptance.



◆ Acceptance with Air Channel is  $n$  times lower.

# Refraction and Number of Primary Photo Electrons (NPPE). Measurements.




◆ Optical Glue in Scintillator Channel results in 1.6 higher NPPE.

## Quality assurance.

### What is the Number of Primary Photo Electrons (NPPE).

#### Test setup

- 1) Standard CDet Block of 14 scintillators + Top & Bottom Trigger telescope.
- 2) Range of cosmic particles  $\sim 4$  cm (normal to slide) ;
- 3) Acceptance  $\pm 20^\circ$  along fibers;  $\pm 2^\circ$  across fibers.



#### We study

pedestal subtracted spectra for `adc(5)` provided:


- 1) good signal from Top and Bottom-
- 2) no signal in two adjacent scintillators-

`adc(14) > 10 & adc(15) > 10`  
`adc(4) < 5 & adc(6) < 5`




# Quality assurance.

## Results for Number of Primary Photo Electrons.




Provided pure statistical fluctuations



$\text{NPPE} = (\text{Mean}/\text{Sigma})^{**2}$

- ◆ Depending on the fit area we find  $\text{NPPE} \approx 30 \pm 4$ .
- ◆ Do we need to improve NPPE ?

# Comparison with Data obtained in 11/06/2015. Cumulative Response of 10 scintillators to cosmic tracks .



$$\text{Mean} \approx N_{\text{ppe}}$$

$$\text{Sigma} \approx \sqrt{N_{\text{ppe}}}$$

$$N_{\text{ppe}} = (\text{Mean} / \text{Sigma})^2$$

$$N_{\text{ppe}} = (16.8 / 3.46)^2$$


$$n_{\text{ppe}} = 4.7 \text{ cm}^{-1}$$

- Expectations with mirror ( $\times 1.6$ ): NPPE  $\approx 30$  along 4 cm side of CDet.
- Agrees with previous slide:  $(30 \pm 4)$ .
- Do we need to improve NPPE ?


# Fabrication of fiber bundles.




Diamond cutting bit




Scintillator side is prepared for cutting



Cutting machine




Machined PNT side




Mounted Bundle

# Quality Assurance.

## Effect of machining technique.



◆ Old technique. Cracks shows up within ~2 monthes.



◆ Improved, but more time consuming technique.  
Shows no cracks after 2 monthes.







## Quality Assurance.


### Effect of cleaning using alcohol containing mixtures.

A bundle of 16 fibers has been used for scintillator block's testing



- ◆ Cleaning fibers using alcohol results in obviously worse fiber transmittance.
- ◆ Damaged 16 fiber bundle was replaced with a new one.
- ◆ The last shows similar damages after insetting into several scintillator blocks.
- ◆ Apparently because scintillator's channels were cleaned using alcohol.
- ◆ What may happen to the inner surface of fiber channels?


Quality Assurance.  
Using Compressed Air Line for Hall B upgrade in 2010-2014.




- ◆ Air flow at room temperature is safe and efficient
- ◆ May be used for CDet construction.



# Central Module Assembling



Nov-2015. Accuracy is of 3 mm



- ◆ PMT Readout and DAQ successfully tested and NPPE estimated.
- ◆ Top+Bottom+Central modules must create uniform surface.
- ◆ Therefore Scintillator **Blocks must be positioned with sub-millimeter accuracy.**
- ◆ Some annex **parts should be designed** for precise adjustment.

# Conclusion and Outlook

- ◆ Fabrication of 14-**Scintillator Blocks** is **finished**.
- ◆ **Fiber Bundle** fabrication is in **progress and improved**.
- ◆ This technique takes **more time**.
- ◆ Using **alcohol** should be avoided.
- ◆ **Delay** due to “screaming” ball bearings **is possible**.
- ◆ Expected nominal **performance of scintillator**: NPPE  $\approx 30$  .
- ◆ It is **sufficient**?
- ◆ **Precision** module **assembling technique** - to be developed.