# MWDC Preparation and Schedule

- Chamber 2 ("half-chamber") had three additional planes added
  - it's now identical to Chamber 3
  - transported on-site in late-September, installed in electron stack for post-move tests
  - currently our only fully-functioning chamber (assuming no problems introduced during transport from UVa)
    - Xin et al. finishing the hook-up this week




# MWDC Preparation and Schedule

- Chambers 1 & 3 both show symptoms of a broken/sagging wire
- Repairs will be done at JLab rather than at UVa
  - eliminate hassle and risk of transporting chambers
  - → faster turn-around
  - establish a repair station here before experiments start
- Clean room tent in EEL 124 has been allocated to us
  - → was used for VDC assembly
  - → a little smaller than UVa space, but workable
  - ⇒ space is cleaned out and ready for the chambers
    ↓ uni-strut hanger rack for the planes is assembled
  - → Mitra, Nilanga, Brad will oversee the repairs
    - we will need at least one or two helpers during disassembly/reassembly stages
      - I'll be in touch...


### MWDC Preparation and Schedule

- Start with Chamber 3 (big chamber)
  - waiting for stiffeners to be welded to long horizontal supports ① on transport frame
    - needed to eliminate a slight sag when chamber is horizontal (worked around at UVa using additional I-beam jacked up under the transport frame)
    - should be done this week or early next week
- Plan to start work on Chamber 3 late next week
  - → hard to judge how long it will take to fix... minimum 3—4 days
- Will start on Chamber 1 after 3 is done




#### Cerenkov Tank Status

- Tank went out to the vendors for fabrication at beginning of September
  - → ~8 week fabrication time
    - done end of October/early November
- All parts will be shipped to JLab (since it's a JLab procurement)
  - → prefer to assemble here if we can locate the space (EEL 124?)
  - ⇒ backup plan: load parts into a U-Haul and drive them up to Temple for assembly and initial tests



#### Cerenkov Mirrors

- Flat mirrors (coated) have arrived
  - → looks good
- Spherical mirrors arrived 2 weeks ago
  - not good
  - → black "protective paint" had been applied over the reflective coating and could not be removed
  - mirrors shipped back to Cosmo Optics for repair
    - "They will make it right."
    - are working on it now, will know how it went by end of week
- Conical mirror blanks complete
  - some minor issues with the surface quality of the blanks as delivered by Model Optics
  - working with Cosmo+Model Optics to resolve this issue





#### Cerenkov Miscellanea

- Cerenkov trigger logic assembled and cabled up
- EDT monitoring system roughed in for BB shower+preshower and Cerenkov trigger logic (working with Kalyan to complete)
  - will also be used as a simulated trigger to test coincidence timing
- Gas system parts-list delivered to Jack
  - → he's been swamped with work in the Hall but hasn't forgotten about us
- HV and signal cables located and stock-piled
  - need 29 ~550ns delay spools for Cerenkov ADC (20 PMT + 9 group sums) will just use a subset of the pi0 delay cables rather than order extra
- PMTs (24) and bases (24) on-site and tested

#### Still needed:

- → ~20 250ns cables to run from the F.E. rack —> weldment racks
- → 1—2 spare remotely adj. discriminator NIM modules (modified P706)
- $\rightarrow C_4 F_{10}$  order should be submitted soon
  - $\fival$ not used until early 2008 since we will do all tests with  $CO_2$  and  $N_2$

### Cerenkov Timeline Summary

### <u>Item</u>

Tank fabrication: late-Oct/early-Nov

Mirrors

→ flat mirrors: completed

⇒ spherical mirrors: 2—12 weeks(?) mid-Nov /

worst case: refab blanks *and* re-coat Jan08

→ conical mirrors: late-Oct/early-Nov

Electron stack frame modifications
 late-Nov(?)

Assembly and leak checking can be done before the end of December

→ if spherical mirrors can be salvaged then we can also do alignment and begin cosmics testing too...

if not, then that will have to wait until Jan. 2008

Est. Completion Date