Transversity Readiness Review **RICH** Upgrade

E. Cisbani

19 Mar 2007

- 1 RICH Overview
- 2 Upgrade (Description, Performance)
- 3 Manpower
- 4 Costs / Funding
- 5 Timeline

EC (INFN)

< 口 > < 同

+ 3 + 4 3 +

nac

Existing RICH schematic view



Main sub-Components

- Mech. Structure: 6 frames + honeycomb cap + 3 pan planes
- Radiator:
 - Liquid C6F14 Freon (15 mm) at Room temperature
 - Vessel: 1.9 × 0.31× Neoceram
 (4 mm) / Quartz (5 mm)
- Proximity Gap: 10 cm
- Photon Detector:
 - MWPC (2 wire planes)
 - 3 PAD PLANES (\sim 11000 pads/chs)
- Dry Methane at STP
- $+\ \mbox{the evaporation facility}$
- (now at Stony=Bro@k University) = ∽٩℃

RICH Upgrade

19 Mar 2007 2 / 1

Present RICH performance at 2.0 \pm 5% GeV/c $\Rightarrow \pi/K$ rejection 1:1000



 At 2.4 GeV/c: $\Delta \theta \sim 4.1\sigma \Rightarrow \pi : K \sim 1 : 140$

 Transversity Requirement: $\pi : K \sim 1 : 1000 \Rightarrow \Delta \theta \ge 4.7\sigma$

 EC (INFN)
 RICH Upgrade

SQA

RICH (Mechanical) Upgrade

Increase (+33%) the photo-detection plane reusing as much as possible the present RICH parts.

- Re-build the last 4 aluminium frames
- reuse 3 + 1 (existing spare) pad planes (90° rotated)
- use old and new electronics (already available)
- implement additional software for the integration of the new electronics into the DAQ
- evaporate Csl on 4 pad planes (instead of 3)

RICH Upgrade



FEM Analysis: $\times 1.3$ (whole detector frame)



FEM tuned to the existing RICH distorsion measurements

EC (INFN)

RICH Upgrade

SQR

FEM Analysis: $\times 1.3$ (Results, in mm)



EC (INFN)

RICH Upgrade

1 19 Mar 2007 6 / 1

DQC2

MC simulation, RICH $\times 1.3$

Performance vs momentum acceptance vs RICH location

• Different collection efficiency along the dispersion plane



Manpower

- Most of the manpower provided by INFN-ISS
- External Italian Company will machine the aluminium frames
- JLab support on:
 - ► Logistics in USA, technical maintenance and installation in Hall A (J. Segal)
 - Minor mechanical work (Mechanical Shop)
 - ► New electronics test and integration into DAQ (A. Camsonne)

	Physicist	Technician			
	Man ×	Month			
Upgrade					
INFN	4	8			
JLab	1.	.5			
Installation					
INFN	1.	1.5			
JLab	.4	.3			

SQA

Costs/Funding (upgrade and installation)

	llab	INFN
Freon	5	5 0
Test Set Up (Rome)	(0 (
Circulation System	() 0
Gap Extender Frame	(0 (
Frame Manufacturing	() 59
Mechanical Support	2	2 0
HV plane	() 5
LV FE electronics	3	30
New RCB board	() 5
Glove Box Upgrade	() 0
Transport Jlab<->Rome	() 5
Transport SBU->Jlab	5	5 0
Pad Plane Shells	3	3 0
Spare Radiator Repairi	(7
	(0 (
Hotel at SBU	3	3 0
Car Rent at SBU (?)	1.5	5 0
	(0 (
Total	22.5	5 81
Values are in kUSD 1 euro = 1.3 USD		

Frame material and manufacturing is the largest cost (official quotation)

FC	INI	E	N
LC	(IIV		N

Milestones

Upgrade

- End Sep 2007: RICH frames Ready, availability of the upgraded frames (and accessories).
- Mid Nov 2007: RICH Assembled in Rome, ready to be shipped to JLab.
- Mid Dec 2007: RICH Ready for installation, all parts of the RICH (included the new electronics) have been tested and ready for integration and installation.

Installation

Starts 2 weeks before obeginning of the Transversity installation, and will takes 8 weeks (test included).

- RICH installation does not interfere with other equipment
- RICH concept is unmodified by the upgrade (different mechanical configuration) ⇒ no new specific test required, no new safety issues

SQA

<ロト <同ト < ヨト < ヨト