

Department _____

Subject Lab Techniques II

Name John SEGAL

Address _____



43-648

Computation Notebook

Dennison Stationery Products Co., Framingham, MA 01701



0 73333 43648 8

75 Sheets
11 $\frac{3}{4}$ " x 9 $\frac{1}{4}$ "
4x4 Quad.

2735DC response photos

5

2735DC & N-277-L linearity

2735DC & N-277-L Jitter 28-105 fC .25ms-15ms
charge injected risetimer

10

2735DC & N-277-L Jitter 28 fC-1050 fC .25ms-15ms
charge injected risetimer

15

20

FPP Straw Tube Ar/Eth 62/38% F_e^{55} and HFA3127amp
LM359
3227SOIC

3227 ~~to AD9624~~ Jitter & Timewalk 28-105 fC .25-15ms

25

Plot of 3227 Jitter 28 fC-105 fC 1.8ms & 5ms rise OpF & 2OpF loading
Plot of N277L, 2735DC & 3227 Timewalk 28 fC-105 fC 1.8ms & 5ms risetime
AD9624 Jitter data 28 fC-105 fC .25ms-15ms

30

Impedance mismatch RG ~~174~~¹⁷⁴ to T'm F

AD9624 A quick look at gain

Inductive pickup on RG-213 - a quick look

35

AMUXTTL and Balun comparison

AMUXTTL channel gain variation

Impedance match RG174 to AMP ribbon coax

40

QPAØ3 gain & noise check (data only - no plots)

43

E711 Fujitsu preamp gain and x-talk
VDC gas gain Ar/CO₂ 75/25%

44
45

Plot of VDC gas gain Ar/CO₂ 75/25
FPP Straw Tubes Gas Gain Ar/CO₂ 75/25
Ar/Eth 62/38 76

50

Plot of FPP Straw Tubes Gas Gain
TDS 744A Demo

55

VDC Analog x-talk

Gain linearity of QPA03, PC, LM359, MB43458, CP01 & 322750IC 60

3227 50IC and FPP Straw Tube

Patch panel evaluation (mine & Detector Group's)

65

TDS 784A Demo

70

VDC Gas Gain (Ar/Eth 62/38)

322750IC linearity ("Little Duke" package)
AWG sizes

75

AWG sizes

VDC gas gain (Ar/Eth 62/38)

PC amp revisited

MAX4100 and OPA650 RG-58 pickoff

80

Secondary Pulsing of TOF PMTs (8575u)

LeCroy 2735 pickoff using MAX435

85

MAX435 pickoff for RG-58

86

87

90

OPA655 pickoff for RG-58

95

2735DC with MAX435 pickoff cards

Pressure drop in $\frac{1}{2}$ " O.D. Poly-flo tubing

100

Propagation velocity of IEEE 802.3 cables

More propagation velocities of IEEE 802.3 cables

Quick look at Molex cable assembly

Further Molex cable investigations

105

Meritec & Molex RG-178 impedance match to RG-174

Photocell/laser diode for positioning - preliminary look

110

Radio Shack photovoltaic cell - quick check

Coherent Instruments Diode laser diode and PVC current

Quick look at sensitivity of laser positioning

115

Bogie motor shaft encoders

120

Diode leakage currents (1N914 and 1N5401)

125

First look at 931B PMT

More 931B investigations

129

Base and tube for background measurements
Setup for measuring charge on a raindrop

130

Charge on a drop tests

Ken's feedback analysis

RG-58C/U, 1/U & RG-59U impedance mismatch demo I

135

First try at a resistive base for 8575 PMT

Further study of 8575 resistive base

140

145

Check of wire chamber signals for Photon Calorimeter

150

152


5
8/17/94
JF

These photos are continued from Lab Techniques I.


In order to look at larger injected charge the attenuation is reduced to 20dB.

The rise time was held fixed while the input step amplitude was varied. 11755C 2.5
10589C 2.25

Rise time not recorded. 9405C 2.0
8239C 1.75
Looking at p. 150 of L.T.I it would appear the rise time is 15 ns.



27350C 20dB @ discr.




27350C 20dB @ discr.

7055C 1.5
4705C 1.0
3535C .75
2355C .5


input step rise time held fixed
at 10ns. Amplitude varied.
Saturation?

V
2.5
2.0
2.0
1.75



27350C 20dB @amp


m
25
20
15
10



27350C 1.75V 20dB @amp

Rise time of input step
varied.
(step pulse is 1μs wide)

Too fast a rise can make the difference. DAC value not recorded, but the same for both photos.
Ch4 is output of Telcrong card through a balun.



Looking at p. 149 & 150 of L.T. I


pulse height input $\frac{mV}{\mu C}$

mV	μC	$\frac{mV}{\mu C}$
1.1 x 20 = 22	23.5	.94 1.88
1.8 x 50 = 90	94	.96 1.92
1.8 x 100 = 180	188	.96 1.92
2.6 x 100 = 260	282	.92 1.84
3.5 x 100 = 350	376	.93 1.86
4.4 x 100 = 440	470	.94 1.88

5ns rise time @ discr.


N277L

3.0 x 20 = 60	23.5	2.55
4.8 x 50 = 240	94	2.55
4.7 x 100 = 470	188	2.50
3.3 x 200 = 660	282	2.34
3.8 x 200 = 760	376	2.02
3.9 x 200 = 780	470	1.66









The program to acquire data is re-written.
Both fast + slow rise times are combined in
one program.







The program to acquire data is re-written.
Both fast + slow rise times are combined in
one program.









DAC ϕ level = 4ϕ for N277L (1.57V)
= 2ϕ for 2735DC (.784V)






@ 1.8V - 1274 / 12 = 106.16666666666667
 1286
 1274
 12
 106.16666666666667



$$\begin{array}{r} 835 \\ - 519 \\ \hline 316 \end{array}$$



1455
 1415
 40
 @ 1.8ns - 1415/40
 ⇒ 22ms walk



985
 - 945

 40


$$\Rightarrow \text{not eval}$$

Timer alk & filter of 2735DC & N-277-L 9/5/84


The program used for pp. 8-12 was re-written to include varying the attenuation (20dB or 40dB). The runs were redone and are consistent with pp. 8-12.

walk @ 1.8ms 56 → 105 fC in $\frac{1450 - 1413}{37 \text{ bins}} \Rightarrow \sim 1.9 \text{ms}$


N277L 0pF 0.60V STEP/40dB ON 4.7pF




N277L 0pF 1.20V STEP/40dB ON 4.7pF




N277L 0pF 1.50V STEP/40dB ON 4.7pF




N277L 0pF 1.75V STEP/40dB ON 4.7pF




N277L 0pF 2.00V STEP/40dB ON 4.7pF



N277L 0pF 2.25V STEP/40dB ON 4.7pF







*plot of p. 14 & p. 16
data*

walk @ 5mA 56 → 105 fC in $\frac{995 - 953}{42 \text{ bins}} \Rightarrow \sim 2.1 \text{ ns}$


N277L 0pF 0.60V STEP/40dB ON 4.7pF




N277L 0pF 1.20V STEP/40dB ON 4.7pF




N277L 0pF 1.50V STEP/40dB ON 4.7pF




N277L 0pF 1.75V STEP/40dB ON 4.7pF




N277L 0pF 2.00V STEP/40dB ON 4.7pF



N277L 0pF 2.25V STEP/40dB ON 4.7pF




plot of p. 13 & p. 15
data




walk @ 1.8ns 280 $\rightarrow$ 1050 fC in $\frac{1371 - 1346}{25 \text{ bins}} \Rightarrow 1.25 \text{ ns}$


N277L 0pF 0.60V STEP/20dB ON 4.7pF




N277L 0pF 1.20V STEP/20dB ON 4.7pF




N277L 0pF 1.50V STEP/20dB ON 4.7pF




N277L 0pF 1.75V STEP/20dB ON 4.7pF



N277L 0pF 2.00V STEP/20dB ON 4.7pF




N277L 0pF 2.25V STEP/20dB ON 4.7pF




walk @ 5ms 280 $\rightarrow$ 1050 fC in $\frac{496}{26}$ bins $\Rightarrow \sim 1.3$ ns


N277L 0pF 0.60V STEP/20dB ON 4.7pF




N277L 0pF 1.20V STEP/20dB ON 4.7pF




N277L 0pF 1.50V STEP/20dB ON 4.7pF




N277L 0pF 1.75V STEP/20dB ON 4.7pF



N277L 0pF 2.00V STEP/20dB ON 4.7pF




N277L 0pF 2.25V STEP/20dB ON 4.7pF




with @ 1.8ms 56 → 105 fC in $\frac{1296}{16 \text{ bins}} \Rightarrow \sim 8 \text{ms}$


2735DC 0pF 0.60V STEP/40dB ON 4.7pF




2735DC 0pF 1.20V STEP/40dB ON 4.7pF




2735DC 0pF 1.50V STEP/40dB ON 4.7pF




2735DC 0pF 1.75V STEP/40dB ON 4.7pF




2735DC 0pF 2.00V STEP/40dB ON 4.7pF









2735DC 0pF 2.25V STEP/40dB ON 4.7pF






*Plot of data on p. 18
and p. 20*

walk @ 5ns 56 → 105 fC is $\frac{828}{16} \text{ bins} \Rightarrow \sim 5 \text{ ns}$




Plot of data on
p. 17 and p. 19




walk @ 1.8ns $280 \rightarrow 1250$ fC is $\frac{1260 - 1252}{8 \text{ bins}} \Rightarrow \sim 4 \text{ mV}$


2735DC 0pF 0.60V STEP/20dB ON 4.7pF




2735DC 0pF 1.20V STEP/20dB ON 4.7pF




2735DC 0pF 1.50V STEP/20dB ON 4.7pF




2735DC 0pF 1.75V STEP/20dB ON 4.7pF









2735DC 0pF 2.00V STEP/20dB ON 4.7pF



2735DC 0pF 2.25V STEP/20dB ON 4.7pF



$\text{walk @ } 5 \text{ ms } 250 \rightarrow 1050 \text{ fC is } \frac{748}{12} \text{ bins} \Rightarrow \sim 6 \text{ ms}$




FPP Straw Tube Ar/Eth 62/38 9/6

Saturday I hooked up one straw tube to gas and +HV. There are small sections of FPP tubes for testing. 1cm diameter. 0.3 mil Alon 4-5 mil mylar. 25.4 μ m (?) diam. wire. Ar/Eth 62/38%. 100 μ Ci Fe^{55} source against the tube. Tube is horizontal. Amp is decoupled from wire by 100 pF. 1 Meg in series w/ HV supply.

1cm straw tube


Fe^{55}




HFA3127 +1670V Ar/Eth 62/38%

This was Saturday.
+/- 12.0V on HFA3127


These two bottom photos were taken Monday. Far end of tube terminated in station photo



+1675V C-40 wire cut. Open end.




+1675V 100pF 360n on far end.




The LM359
supply = +11V


LM359 +16.74V open end




LM359 +16.76V 22pF & 360Ω term.



LM359 +16.75V 1000pF & 360Ω term.



3227 SOIC +1676V open end



3227 SOIC +1676V 1000pF + 360Ω term

The 3227 SOIC amp
~~12V~~ supplies

Bootstrapping not in
 place. See p. 63 & 64
 of this book.
 2/1/95 J.S.


10/4 Timewalk & jitter of 3227 amp 4AD9624

JS


~~same program used~~ This was done on Sep. 25

The program used on pp 13-20 was modified to accommodate a single ended signal being run into a Phillips 7106 discriminator. Setup similar to that for pp. 13-20 except for 7106 discriminator.


3227 0pF 0.60V STEP/40dB ON 4.7pF




3227 0pF 1.20V STEP/40dB ON 4.7pF




3227 0pF 1.50V STEP/40dB ON 4.7pF




3227 0pF 1.75V STEP/40dB ON 4.7pF




3227 0pF 2.00V STEP/40dB ON 4.7pF




3227 0pF 2.25V STEP/40dB ON 4.7pF




3227 0pF 0.80V STEP/40dB ON 4.7pF




3227 0pF 1.20V STEP/40dB ON 4.7pF




3227 0pF 1.50V STEP/40dB ON 4.7pF




3227 0pF 1.75V STEP/40dB ON 4.7pF




3227 0pF 2.00V STEP/40dB ON 4.7pF




3227 0pF 2.25V STEP/40dB ON 4.7pF




3227 20pF 0.60V STEP/40dB ON 4.7pF




3227 20pF 1.20V STEP/40dB ON 4.7pF




3227 20pF 1.50V STEP/40dB ON 4.7pF




3227 20pF 1.75V STEP/40dB ON 4.7pF




3227 20pF 2.00V STEP/40dB ON 4.7pF




3227 20pF 2.25V STEP/40dB ON 4.7pF




3227 20pF 0.60V STEP/40dB ON 4.7pF




3227 20pF 1.20V STEP/40dB ON 4.7pF




3227 20pF 1.50V STEP/40dB ON 4.7pF




3227 20pF 1.75V STEP/40dB ON 4.7pF




3227 20pF 2.00V STEP/40dB ON 4.7pF




3227 20pF 2.25V STEP/40dB ON 4.7pF




3227 0pF




3227 0pF




3227 20pF




3227 20pF




3227 0pF




3227 0pF




3227 20pF




3227 20pF




N277L 0pF SEP 3




N277L 0pF SEP 3




27350C 0pF SEP 3




27350C 0pF SEP 3




3227 0pF




3227 0pF




9624 0pF 0.60V STEP/40dB ON 4.7pF




9624 0pF 1.20V STEP/40dB ON 4.7pF




9624 0pF 1.50V STEP/40dB ON 4.7pF




9624 0pF 1.75V STEP/40dB ON 4.7pF




9624 0pF 2.00V STEP/40dB ON 4.7pF




9624 0pF 2.25V STEP/40dB ON 4.7pF




9624 0pF 0.60V STEP/40dB ON 4.7pF




9624 0pF 1.20V STEP/40dB ON 4.7pF




9624 0pF 1.50V STEP/40dB ON 4.7pF




9624 0pF 1.75V STEP/40dB ON 4.7pF





9624 0pF 2.00V STEP/40dB ON 4.7pF



9624 0pF 2.25V STEP/40dB ON 4.7pF




10/27 Impedance Mismatch RG¹⁷⁴ to T_{in}F






Ch2
Upper trace is with coupling pins
Lower trace is 2 sections
of T_{in}F

open end (pulser wants to see
50Ω load. Ringing)


ch1
Earlier trace is with
coupling pins
Later trace is 2 sections
of T_{in}F




2 sections of T_{in}F



11/6 AD9624 Quick Look




(This was done a few weeks ago)



1.8ns rise on 40dB + 4.7pF

• 6V step
 • 1.5V step
 • 2.25V step



Same as above except 5ns rise


Quick Look Inductive Pickup RB-213

Intercomp 50Ω Low Loss Coaxial Cable


35

11/6

Put a roll ($\sim 3/4$ full) of RB-213 in the detector group's Helmholtz coil. Roll is from Bob Michaels cable delay testing. With the Sorenson 55-180 power supply in current mode an ~ 8 Hz oscillation can be generated. Voltage limit must be set low enough to prevent supply from settling down. With supply at 20A;



CUT is roughly centered $\pm 6"$




Shortly after flipping supply port. Dips & drops after a couple of minutes.


Supply voltage limit adjusted to provide steady oscillations. See next page.

26A @ 6.0V to coil
(read from supply display)



Voltage limit set to 6.0V. Current set to 20A. After turn on get steady oscillations



Scope removed from circuit. Cable ends connected together with a barrel connector. FET probe used to hook at "+" output of supply. GND clip not connected to anything.



Disassembled setup.
 Reassembled to try 50Ω in series w/ cable.



With supply in voltage mode @ 0.5V get 3A read from supply display
 6.0V 5A
 1.5V 7A

11/20
JD


AMUX TTL + Balun Comparison

The PC amp is used to check responses to a differential pulse.

PC amp driven by a 2.25V step pulse
1.8ns rise & fall from PG2012 pulser.


40dB on 10pF for input charge.

$V_{supply} = 11.6V$




6" of flat cable pair
Single core balun
+15ns RG174

Response to both rising
& falling edges



6" of flat cable pair
Single double core
balun and 15ns RG174






1 section of T_{in}F
 2 sections of T_{in}F
 to 4 MUX TTL
 05 ms RG174

The amplitude of each channel is measured with the same input. 1 section of T_{in}F is moved from channel to channel. (line to line)


66.6 mV
 67.0
 66.8
 66.6
 67.6
 68.2
 67.8
 66.8
 66.6
 67.0
 65.6
 66.6
 66.2
 65.6
 64.0
 65.4













11/20

R6-174 to AMP Ribbon Coax Impedance Match
Same setup as p. 32.Coil of 50 Ω ribbon coax from AMP is testedDriving shield
Center cond. grounded.Driving central
conductor.
shield grounded.













QPAØ3 Gain + Noise (UVA layout) 12/4
 Setup is similar to p 118 of Lab Techniques I.

Program is rewritten as AMPTEST.FOR to incorporate fast + slow risetimes (.25ms $\rightarrow$ 15ms).






$$V_{\text{supply}} = 3.50V$$




$$V_{\text{supply}} = 3.75V$$


QPA03 0pF 0.60V STEP/40dB ON 4.7pF




QPA03 0pF 1.20V STEP/40dB ON 4.7pF




QPA03 0pF 1.50V STEP/40dB ON 4.7pF




QPA03 0pF 1.75V STEP/40dB ON 4.7pF




QPA03 0pF 2.00V STEP/40dB ON 4.7pF




QPA03 0pF 2.25V STEP/40dB ON 4.7pF




QPA03 0pF 0.60V STEP/40dB ON 4.7pF




QPA03 0pF 1.20V STEP/40dB ON 4.7pF




QPA03 0pF 1.50V STEP/40dB ON 4.7pF




QPA03 0pF 1.75V STEP/40dB ON 4.7pF



QPA03 0pF 2.00V STEP/40dB ON 4.7pF



QPA03 0pF 2.25V STEP/40dB ON 4.7pF




$$V_{\text{supply}} = 4.09V$$


E711 Preamp Gain

Fujitsu chips. Amp used at Fermilab
on various experiments (e.g. E771)

MB 43458




0V input step voltage



10mV 10ns

4V
3V
2V
1V

Looking at channel 3 of the preamp



1
2
4

With channel 3 of the preamp driven with a -4V step there are the outputs of channels 1, 2 and 4 of the preamp. Channels are on the same fujitsu chip.



The Continuous Electron Beam Accelerator Facility

Hall A Prototype VDC Gas Gain Measurements

January 10, 1995

H. Fenker and J. Segal

This report documents results obtained when we measured the gas gain of the Hall A Prototype Vertical Drift Chamber (VDC). The purpose of the measurement was to determine the gain to within about 50% in order to facilitate estimates of the aging rate of the chamber at the required operating voltage. The operating voltage (cathode voltage) required for efficient (or precise) chamber behavior varies with the electronic threshold. Typically the latter is set as low as practical but above the point at which the electronics oscillates. Then the cathode voltage is raised until efficient operation is achieved. If the required cathode voltage is then too high for stable or long term operation of the detector, one must improve the electronic environment (grounding, shielding, etc.) or install improved electronics (a preamplifier, for example).

The gain measurement technique we used was to observe the total charge produced in an avalanche which was initiated by an X-ray from an ^{55}Fe source. In the 75/25 Ar/ CO_2 gas used, the number of ion pairs created by such a 5900 eV X-ray is

Gas	Ionization Potential	Fraction	Ion Pairs
Argon	26 eV	0.75	170
CO_2	33 eV	0.25	45
Total			215.

Thus, if we observed 21,500 electrons we would say the gas gain was 100.

In order to actually observe the charge signal it is necessary to use a low-noise amplifier at the output of the wire chamber. We used a EG&G 142PC preamplifier which is specified to charge sense with a gain of 6.5 V/pC. To check this we constructed the circuit shown in Fig. 1 and measured the preamplifier gain to be 4.8 V/pC. This measurement and the manufacturer's specification agree within our tolerance. At this point we verified certain features of the preamplifier and test circuit as:

- short rise time (~ 30 ns);
- amplifier output linear with attenuator input up to almost 6V at the output;
- output peak voltage insensitive to pulser output width or risetime (< 100 ns)
- output returns-to-baseline in about 75 μs , as specified.

The chamber gain can now be measured in a straightforward manner. The signal from one anode wire was coupled directly (via about 10cm of RG59) to the preamplifier input. With an ^{55}Fe source illuminating the chamber two bright bands were clearly observed on the oscilloscope. The higher one corresponds to the X-ray peak (5.9 keV), while the lower one is the Argon (photoluminescence) escape peak at about $(5.9 - 3.2 = 2.7)$ keV. Fig. 2 is




Figure 1. The Circuit Used to Measure the Gain of the 142PC Preamplifier.

a photograph of the QVT spectrum (taken in 'V' mode) from the observation made with $V_{\text{cathode}} = 3000 \text{ V}$.

Figs. 3a - 3f are 'scope photographs made at the indicated cathode voltages. The middles of the X-ray bands were estimated by eye on these images and the adjustable cursor placed there to facilitate measuring the average peak voltage. The positions thus determined are indicated on the photographs. The measurements are presented in Table 2 and Fig. 4.

Cathode HV	V_{peak} (mV)	Q_{meas} (fC)	Gas Gain
2900	386	80	$2.5\text{E}+3$
3000	630	131	$4.1\text{E}+3$
3100	1020	212	$6.6\text{E}+3$
3200	1660	345	$10.8\text{E}+3$
3250	2110	439	$13.7\text{E}+3$
3300	2880	600	$18.8\text{E}+3$

Table 2. Results of the Output Pulse Observations and Conversion into Wire Chamber Gas Gain for 75/25 Ar/CO₂.




Figure 2. Peak-Voltage Spectrum Obtained with a QVT for Fe^{55} Drift Chamber Pulses with 3000 V on the Cathodes.




Figure 3a. 2900 V




Figure 3b. 3000 V




Figure 3c. 3100 V




Figure 3d. 3200 V




Figure 3e. 3250 V





Figure 3f. 3300 V



• Figure 4. VDC Gas Gain as a Function of Cathode Voltage


Measured gain of 142PC preamp

50ms leading edge on step


900V step from 140dB on 4.7pF = 42fC

~4div x 50mV/div $\approx$ 200mV peak output
 $\Rightarrow$ 4.8V/pC

42fC x 6.5mV/fC $\approx$ 2.73mV
 (close)



Ioniz. Pot. for Ethane (C_2H_6) $\frac{24eV}{1.6eV}$ (average)




Ar/Eth 62/38% 1400V

Frame As/CO₂

~~1130~~ 385

~~275c~~ 80fc

 ~~$G = 2.3 \times 10^3$~~ ← from Ar/CO_2
 $G = 2.1 \times 10^3$ 

1450V


129fc

$$G = 3.8 \times 10^3$$
$$G = 3.4 \times 10^3$$


6405C

$G=1.9 \times 10^{-4}$

$G=1.7 \times 10^{-4}$



1600V




1500V


2105C

$G=6.1 \times 10^{-3}$

$G=5.6 \times 10^{-3}$



1650V



1550V

3775C

$G=1.1 \times 10^{-3}$

$G=7.4 \times 10^{-4}$


10385C

$G=3.8 \times 10^{-4}$


$G=2.7 \times 10^{-4}$

24fc
 $G = 7 \times 10^3$


36fc

 $G = 1 \times 10^3$



Ar/KO₂ 75/25 1300V



1350V



1400V



1450V

60fc


 $G = 1.7 \times 10^3$

101fc


 $G = 2.9 \times 10^3$

438fc

$G=1.3 \times 10^4$



1600V




1500V

166fc


$G=4.8 \times 10^2$

746fc

$G=2.2 \times 10^4$




1650V



1550V

269fc

$G=7.8 \times 10^2$



1175 FC

$$G = 3.4 \times 10^4$$

1700V

For Ar/Eth 62/38

assuming 62% of interactions are with Ar and
38% are with Eth

if x = total ion pairs produced
average energy for ion pair production is for

$$\text{Ar} = 26 \text{ eV}$$

$$\text{Eth} = 24 \text{ eV}$$

$$\text{CO}_2 = 33 \text{ eV}$$

$$(.62x)(26 \text{ eV}) + (.38x)(24 \text{ eV}) = 5900 \text{ eV for Fe}^{55}$$

$$x = \frac{5900}{16.12 + 9.12}$$

$$\approx 234 \text{ ion pairs}$$

for Ar/CO₂ 75/25


$$(.75x)(24 \text{ eV}) + (.25x)(33 \text{ eV}) = 5900 \text{ eV}$$

$$x = \frac{5900}{19.5 + 8.25}$$


$$\approx 213 \text{ ion pairs (Howard got 215 on p. 46)}$$

use 215 for G calculation

FPP Straw Tube Gas Gain




FPP Straw Tube Gas Gain





1/28 Tektronix TDS 744A Demonstration

The TDS 744A is used to look at one of the FPP straw tubes with Av/EHV 62/38% and the 322750IC amplifier




Substrate bootstrap is removed!

2465B scope
Fe⁵³ on chamber




same as above

Looking at the chamber output with the TDS744A. It is possible to see rate variations as the ^{55}Fe source is waved over the chamber. See pictures below. Both were taken at a fairly low rate. At higher rates the traces tend to wash out. Shortest persistence time is 250ms. Perhaps a shorter persistence and more "grey scaling" would improve the display.



TDS 744A
 ^{55}Fe on chamber
 Shows tendency to
 "washout"




One of the better
 shots.
 Same setup as
 above photo

1/30 VDC Crosstalk - A Quick Look
 Done ~1/23
 Looking at VDC with Fe^{55} Ar/ CO_2 75/25
 (welding grade)
 Using UVA-QPAD3 preamp.





Gain adjusted so amp is not saturating.
 Set to 3300V on both cathodes. Afterwards
 I checked and found they were at 3600V.

Output of amp through a balun and 6 m of
 RG174. Single core balun on Ch.3. Small copper
 pipe, 2 core balun on ch.3.



checked on the
 2467B to verify
 polarity of signal.

The TDS644A is set to average 64 traces.
 The Channels 3 & 4 are of adjacent wires.
 Taken from 2 different sets of 2 wires (in same
 set of 16 wires). 2 different QPAD3 chips. One
 each time.



1/30

Gain Linearity of Miss Amps







Pulse step size is varied and attenuation is also varied.


Just for reference →

Summary of results
all 3 plots are of same data set.


OPA03 11 step 40dB 3.5V supply




Amp responses to 5V step 40dB




CP01




LM359




PC






Fujitsu MB43458



3227 SOIC substrate bootstrap



QPA03




3227SOIC & FPP Straw Tube

2/1
JA




Source in
mid point
of tube.

similar setup to p. 21




Ar/CO₂ 75/25


+14V (HV filter used from p. 50)




The feedback capacitor to "bootstrap" the substrate is removed. All three photos are of the same thing, just different scales. Compare with photos on p. 23 of this book.



1676V



1676V




1676V

Patch Panel Evaluation

PG 2012



T05644A








all R658C/U


Using Ch2 of PG2012
 5ms fixetime
 width = 2000ms
 1/64 step

5ms replaced with
 another 45ms of
 R658C/U






Same as previous photo.
Ch 12 (worst case channel)



Ch 12


Same setup except
this is detector group's
multilayer patch panel
board.

Ch 15 is best case channel




Det Ch 15


Same as above
Ch 16 is worst case
channel




Det Ch 16




2 layer Ch2=16 Ch4=15



2 layer Ch2=12 Ch4=11



Det. Drive 16 Ch2=16 Ch4=15



Patch panel
Ch4 is adjacent channel
off patch panel. Next to
driven channel.


Best case channel

Same as above except
worst case channel

Also some tiny bit of
x-talk on channel 14!
Oh, very tiny, but still...
~1mV
even if 13 is terminated
with 50Ω.

Same as above except
detector groups patch
panel. Best case channels


A quick check & all channels
seem similar.



While doing the
second photo on p. 66
I found an anomalous
RG174 cable. Labeled "2"


←
same setup as middle photo
on p. 66

cable shows M17/119-RG174
in yellowish lettering



cable "2"

same as above except
expanded time scale





cable "6" "4" & unlabeled are similar

Cable "6" shows M17/119-RG174
in white lettering


Cables "4" & unlabeled show
RG174 A/U on them

70
2/16
48

TDS 784A scope Demo





scope on dustav
100 μ Ci source 4/1990
~1cm from tube.
scope stopped at a random
time by front panel
button. Grey scale.
250ms persistence



same source @ ~4cm⁺
or 5cm?
(queried by eye)

500 μ Ci source 11/16/94
@ ~ 1cm



Similar to above except
display intensity is
reduced.


2/23

VDC Gas Gain Ar/Eth 62/38%


Similar setup to p. 46 of this book.
Full size VDC. All three planes at the same
voltage. 100M Ω in series with each plane

Time started is 9PM. Reach 3400V @ ~9:20PM
Gas flowing @ ~3 ft³/hr since 6PM on 2/22.
Looking at fire ~ middle of top plane. Gas input
is to the top plane. Source ~ center of face.


2900V




3000V



↓ 3100V ↓




↓ 3200V ↓




3300V





3400V




↓ 3500V ↓



↓ 3550V ↓



2/26 322750IC in "Little Duke" package & Linearity




TDS644A set to average 64 traces. Use low measurement on channel to get pulse height.

		30ns	40ns	50ns	5ns	10ns	15ns	20ns
38dB	.8V	15	12	9	79	53	36	26
47dB	1.0	19	13	12	99	68	45	34
71dB	1.5	31	21	17	154	105	71	47
118	2.5	53	37	29	279	192	127	91
165	3.5	77	51	41	398	281	185	133
212	4.5	102	70	54	522	366	244	176
259	5.5	126	90	66	650	450	306	190
306	6.5	150	110	86	780	532	366	268
353	7.5	174	114	102	916	632	428	258
400	8.5	194	130	102	1044	724	490	302

scope measurement not set up correctly

	IC	5ns	10ns	15ns	20ns	30ns	40ns	50ns
1	38,000	78,000	52,000	37,000	27,000	18,000	13,000	10,000
2	47,000	98,000	68,000	46,000	34,000	22,000	16,000	13,000
3	71,000	158,000	107,000	72,000	52,000	33,000	24,000	20,000
4	118,000	278,000	193,000	128,000	90,000	59,000	42,000	34,000
5	165,000	398,000	278,000	184,000	133,000	86,000	63,000	50,000
6	212,000	524,000	365,000	244,000	181,000	115,000	84,000	63,000
7	259,000	650,000	452,000	306,000	224,000	142,000	102,000	82,000
8	306,000	780,000	540,000	366,000	270,000	174,000	124,000	100,000
9	353,000	912,000	632,000	428,000	316,000	202,000	146,000	118,000
10	400,000	1044,000	724,000	490,000	364,000	236,000	170,000	136,000
11	447,000	1176,000	824,000	562,000	412,000	270,000	198,000	158,000



Technical Information

Table 1

Solid Bare Copper Wire American Wire Gauge

Gage (ASTM B8)	Nominal Diameter in.	Area sq. in.	Weight lb. per 1000 ft.	Resistance ohms per 1000 ft.
11	.0807	.5067	34.9	1.68
12	.0658	.3306	22.1	2.62
13	.0527	.2107	13.9	4.08
14	.0419	.1366	8.8	6.41
15	.0330	.0870	5.5	10.1
16	.0260	.0533	3.4	16.1
17	.0209	.0336	2.1	25.3
18	.0162	.0213	1.3	39.5
19	.0127	.0132	.8	61.8
20	.0100	.0081	.5	98.1
21	.0079	.0051	.3	156.1
22	.0063	.0032	.2	244.1
23	.0051	.0020	.1	395.1
24	.0040	.0013	.0	608.1
25	.0032	.0008	.0	924.1
26	.0025	.0005	.0	1400.1
27	.0020	.0003	.0	2124.1
28	.0016	.0002	.0	3200.1
29	.0012	.0001	.0	4840.1
30	.0010	.0001	.0	7260.1
31	.0008	.0000	.0	10920.1
32	.0006	.0000	.0	16320.1
33	.0005	.0000	.0	24480.1
34	.0004	.0000	.0	36720.1
35	.0003	.0000	.0	55080.1
36	.0002	.0000	.0	82560.1
37	.0001	.0000	.0	123840.1
38	.0001	.0000	.0	185760.1
39	.0001	.0000	.0	278640.1
40	.0001	.0000	.0	417920.1

Information from National Bureau of Standards Copper Wire Tables—Handbook 100.

Technical Information

1 Passes

Stranded Tinned Copper Wire American Wire Gauge

Gage (ASTM B8)	Nominal Diameter in.	Area sq. in.	Weight lb. per 1000 ft.	Resistance ohms per 1000 ft.
11	.0807	.5067	34.9	1.68
12	.0658	.3306	22.1	2.62
13	.0527	.2107	13.9	4.08
14	.0419	.1366	8.8	6.41
15	.0330	.0870	5.5	10.1
16	.0260	.0533	3.4	16.1
17	.0209	.0336	2.1	25.3
18	.0162	.0213	1.3	39.5
19	.0127	.0132	.8	61.8
20	.0100	.0081	.5	98.1
21	.0079	.0051	.3	156.1
22	.0063	.0032	.2	244.1
23	.0051	.0020	.1	395.1
24	.0040	.0013	.0	608.1
25	.0032	.0008	.0	924.1
26	.0025	.0005	.0	1400.1
27	.0020	.0003	.0	2124.1
28	.0016	.0002	.0	3200.1
29	.0012	.0001	.0	4840.1
30	.0010	.0001	.0	7260.1
31	.0008	.0000	.0	10920.1
32	.0006	.0000	.0	16320.1
33	.0005	.0000	.0	24480.1
34	.0004	.0000	.0	36720.1
35	.0003	.0000	.0	55080.1
36	.0002	.0000	.0	82560.1
37	.0001	.0000	.0	123840.1
38	.0001	.0000	.0	185760.1
39	.0001	.0000	.0	278640.1
40	.0001	.0000	.0	417920.1

Information from National Bureau of Standards Copper Wire Tables—Handbook 100.

STRANDED TINNED COPPER WIRE TABLE OF DATA


AWG Size	Stranding	Nom. O.D. of Strand	Approx. O.D.	Circular MIL Area	Wt. Lbs./1000 Ft.	Ohms Per 1,000 Ft.*
36	7/44	.002	.006	28.00	.085	371.0
34	7/42	.0025	.0075	43.75	.132	237.0
32	7/40	.0031	.008	67.27	.203	164.0
32	19/44	.002	.009	76.00	.230	136.4
30	7/38	.004	.012	112.00	.339	103.2
30	19/42	.0025	.012	118.75	.359	87.3
28	7/36	.005	.015	141.75	.529	64.9
28	19/40	.0031	.018	182.59	.553	56.7
27	7/35	.0056	.018	219.52	.664	51.47
26	7/34	.0063	.019	277.83	.841	37.3
26	10/36	.0050	.021	250.00	.757	41.48
26	19/38	.0040	.020	304.00	.920	34.43
24	7/32	.008	.024	448.00	1.356	23.3
24	10/34	.0063	.023	396.90	1.201	26.09
24	19/36	.0050	.024	475.00	1.430	21.08
24	41/40	.0031	.023	384.40	1.160	25.59
22	7/30	.0100	.030	700.00	2.120	14.74
22	19/34	.0063	.031	754.11	2.28	13.73
22	26/38	.0050	.030	650.00	1.97	15.94
20	10/30	.0100	.035	1000.00	3.025	10.32
20	19/32	.0080	.037	1216.00	3.68	8.63
20	26/34	.0063	.036	1031.94	3.12	10.05
20	41/36	.0050	.036	1025.00	3.10	10.02
18	7/26	.0159	.048	1769.60	5.36	5.86
18	16/30	.0100	.047	1600.00	4.84	6.48
18	19/30	.0100	.049	1900.00	5.75	5.46
18	41/34	.0063	.047	1627.29	4.92	6.37
18	65/36	.0050	.047	1625.00	4.91	6.39
16	7/24	.0201	.060	2828.00	8.56	3.67
16	19/29	.0113	.058	2426.30	7.35	4.27
16	26/30	.0100	.059	2600.00	7.87	4.00
16	65/34	.0063	.059	2579.85	7.81	4.02
16	105/36	.0050	.059	2625.00	7.95	3.99
14	7/22	.0253	.073	4480.0	13.56	2.31
14	19/27	.0142	.073	3830.4	11.49	2.70
14	41/30	.0100	.073	4100.0	12.40	2.53
14	105/34	.0063	.073	4167.5	12.61	2.49
12	7/20	.0320	.096	7168.0	21.69	1.45
12	19/25	.0179	.093	6087.6	18.43	1.70
12	65/30	.0100	.095	6500.0	19.66	1.75
12	165/30	.0063	.095	6548.9	19.82	1.58

AWG Size	Stranding	Nom. O.D. of Strand	Approx. O.D.	Circular MIL Area	Wt. Lbs./1000 Ft.	Ohms Per 1,000 Ft.*
10	37/26	.0159	.115	9353.6	28.31	1.11
10	49/27	.0142	.116	9878.4	29.89	1.09
10	105/30	.0100	.116	10,530.0	31.76	.98
8	49/25	.0179	.147	15,699.6	47.53	.67
8	133/29	.0113	.147	16,984.1	51.42	.61
8	655/36	.0050	.147	16,625.0	49.58	.62
6	133/27	.0142	.184	26,812.8	81.14	.47
6	259/30	.0100	.184	25,900.0	78.35	.40
6	1050/36	.0050	.184	26,250.0	79.47	.386
4	133/25	.0179	.232	42,613.0	129.01	.243
4	259/27	.0143	.232	52,214.4	158.02	.20
4	1666/36	.0050	.232	41,850.0	126.10	.25
2	133/23	.0226	.292	67,936.4	205.62	.152
2	259/26	.0159	.292	65,475.2	198.14	.16
2	665/30	.0100	.292	66,500.0	201.16	.157
2	2646/36	.0050	.292	66,150.0	200.28	.157
1	133/22	.0253	.328	85,133.3	257.60	.121
1	259/25	.0179	.328	82,983.6	251.20	.125
1	817/30	.0100	.328	81,700.0	247.10	.127
1	2109/34	.0063	.328	83,706.2	253.29	.124
1/0	133/21	.0285	.368	108,035.9	327.05	.096
1/0	259/24	.0201	.368	104,636.0	316.76	.099
1/0	1045/30	.0100	.368	104,500.0	316.11	.099
1/0	2660/34	.0063	.368	105,575.4	319.47	.098
1/0	4214/36	.0050	.368	105,350.0	318.96	.098
2/0	133/20	.0320	.414	136,192.0	412.17	.077
2/0	259/23	.0226	.414	132,297.2	400.41	.077
2/0	1330/30	.0100	.414	133,000.0	402.33	.077
2/0	3325/34	.0063	.414	131,969.2	399.33	.077
2/0	5292/36	.0050	.414	132,300.0	400.55	.077
3/0	259/22	.0253	.464	163,195.9	501.7	.062
3/0	427/24	.0201	.464	172,508.0	522.2	.059
3/0	1661/30	.0100	.464	166,100.0	502.45	.062
3/0	4256/34	.0063	.464	166,920.6	511.15	.061
3/0	6713/36	.0050	.464	167,825.0	508.11	.061
4/0	259/21	.0285	.522	210,385.7	638.88	.049
4/0	427/23	.0226	.522	218,111.6	660.01	.047
4/0	2104/30	.0100	.522	210,400.0	636.46	.049
4/0	5320/34	.0063	.522	211,150.8	638.89	.049
4/0	8512/36	.0050	.522	212,800.0	644.27	.049


* Resistance in Ohms per 1000 ft. at 68°F (20°C)


3/27

• Gas Gain (234 ion pairs) (calculated for Ar/Eth 62/38)

**VDC Gas Gain for
Argon(62%)/Ethane(38%)**

• Gas Gain

**VDC Gas Gain for
Argon(62%)/Ethane(38%)**







4/10/95


PC Amp Revisited

PC Amp from p. 30 of Vol I ~~has~~
has the remaining 15 channels stuffed

The one
channel is
left as on
p. 30 of
Vol I




Max 4100 and OPA650 RG-58 pickoffs
 in March '96 8013B




Pomona 5696-72 →

16ns of RG-58
 either barrel connector or
 pickoff in a small Pomona box



No MAX4100


Barrel connector in place.



MAX4100


MAX4100 in small pomona box
 inserted. DC power is on.

DC power is off




MAX4100

OPA650 in small pomona box
is inserted. DC power is on.



OPA650

DC power is off.






OPA650

4/19
15:4
Thurs


Secondary Pulsing on TOF PMTs

Amongst other problems we have after pulsing of the PMT's for the TOF scintillators.



Tek Stop: 500MS/s

346 Acqs

△: 518ns
●: 538ns

-1900V

19 Apr 1996
15:45:56

4/21/96 LeCroy Pickoff Using MAX435


Comparison of MAX435 with FET probe.
MAX435 is on pickoff board made for differential pickoff.

Long lead in standard board setup. Short lead has input tracer trimmed as far as board will allow. Grounded input has ~.75" 28GA wire.


Power is derived off LeCroy card.

Output is through balun with ~5m of R6174

This was actually done on 3/31.



Etched a ground plane circuit board to sit on the LeCroy card. This will give a minimal lead length for both + & - inputs. - input is grounded input. R_{SET} is $7.5\text{ k}\Omega$.





Ch3 of scope is FET probe at + input of MAX435 card. Scope set to average 10 traces.


Ch4 in Balun
output
Ch3 in FET
probe
Both on
channel 1 of
the 2735
Channel 1 in
pulser

Ch3 in FET at
407 input of
channel 1 of
2735 (channel
2 in pulser)
R1 in FET at
467 input of
channel 1 of 2735
with MAX435 card,
also (channel 1
in pulser)

~10% loss in
pulse height
due to MAX435









4/25/96 MAX435 Pickoff for R6-58
JS











Traces are average of 16





for MAX435 $R_{gain} = 200 \Omega$ $R_{load} = 51.1 \Omega$ $R_{set} = 7.5 K \Omega$
 $V = 9V$ battery












Tek Stop: 500MS/s

83 Acqs




power OFF

25 Apr 1996
11:09:05

Tek Stop: 500MS/s


74 Acqs

25 Apr 1996
11:07:46

$$\frac{V_p}{V} = \frac{360}{1000} = .36$$

Tek Stop: 500MS/s


60 Acqs

25 Apr 1996
11:08:23

$$\frac{V_p}{V} = \frac{360}{1080} = .33$$


Tek Stop: 500MS/s

46 Acqs




Tek Stop: 500MS/s

53 Acqs




Tek Stop: 500MS/s

77 Acqs




Tek Stop: 500MS/s

56 Acqs




Power in OFF
DUT in place


Tek Stop: 250MS/s 89 Acqs






Tek Stop: 500MS/s 44 Acqs




Tek Stop: 250MS/s 102 Acqs






OPAG55 Pickoff for RG-58

$$5/25$$


all cables are ~~10~~ m of
RG-58C/U (or something close)
D+V 20K



DIP package used

SPECIFICATIONS


 $\beta_n = 25$ G, $V_n = 15$ V, $I_{k,n} = 100$ A and $I_{\text{L},n} = 100$ A, unless otherwise noted. $I_{k,n} = 0$ for $G = 1$.

PARAMETER	CONDITIONS	OPAMP818, U			UNIT
		MIN	TYP	MAX	
FREQUENCY RESPONSE					
Frequency Response	Gain = 10V/V, V_{DS} = 200mV/p-p		400		MHz
Gain Bandwidth Product	Gain = 20V/V, V_{DS} = 200mV/p-p		185		MHz
	Gain = 100V/V, V_{DS} = 200mV/p-p		57		MHz
Common-Mode Rejection	Gain = 100V/V, V_{DS} = 200mV/p-p		24		dB
Slew Rate	$G = -1$, 1V Step	210	240		V/μs
Over Temperature	0.2V Step	700			V/μs
Rise Time	$G = -1$, 1V Step		1		ns
Fall Time	$G = -1$, 1V Step		1		ns
Settling Time 0.01%	$G = -1$, 1V Step		8		ns
0.1%	$G = -1$, 1V Step		8		ns
0.5%	$G = -1$, 1V Step		90		ns
Transition 10% to 90% Rise Time	$V_{DS} = 1$, 1V, $R_L = 100k$	75			μs
Differential Gain	3.5MHz, 0 to 14V, $R_L = 150k$		0.006		dB
Differential Phase	3.5MHz, 0 to 14V, $R_L = 150k$		0.009		degrees
Linearity 0.1% THD Distortion	$G = -2$, 200p-p		0		dB
OFFSET VOLTAGE					
Input Offset Voltage	$V_{DS} = 4.50V$ to $5.50V$		21	12	mV
Over Temperature		55	70		mV/°C
Power Supply Rejection (V_{DS})		50	65		dB
Common-Mode Rejection (V_{DS})					dB
INPUT BIAS CURRENT					
Input Bias Current	$V_{DS} = 0V$				nA
Over Temperature	$V_{DS} = 0V$		-5	-50	nA
Input Offset Current	$V_{DS} = 0V$			-3.2	nA
Over Temperature	$V_{DS} = 0V$			-50	nA
				-13.2	nA
NOISE					
Input Voltage Noise					nV/√Hz
1kHz Density, $f = 100Hz$			20		nV/√Hz
$f = 1kHz$			8		nV/√Hz
$f = 10kHz$			6		nV/√Hz
Integrated Voltage Noise					nV/√Hz
10Hz to 100kHz			60		nV/√Hz
Input Bias Current Noise					nV/√Hz
Current Noise Density, $f = 10Hz$ to $100Hz$					nV/√Hz
INPUT VOLTAGE RANGE					
Common-Mode Input Range			1.3	A	V _{DS}
Over Temperature					
Common-Mode Rejection	$V_{DS} = 10.5V$	22.5	12.75		dB
INPUT IMPEDANCE					
Differential					V
Common-Mode					V
Open-Loop Gain	$V_{DS} = 12V$, $R_L = 100k$				dB
Common-Mode Voltage Gain	$V_{DS} = 12V$, $R_L = 100k$	53	58		dB
OUTPUT					
Voltage Output	$R_L = 100k$, $G = -1$				V
Over Temperature			13.4		V
Common Output		130			V
Over Temperature		128			V
Short-Circuit Output Current			1140		mA
Output Resistance	$0.1MHz$, $G = -1$		0.04		Ω
POWER SUPPLY					
Standby Operating Voltage			15		V
Operating Voltage Range	I_{DS} to I_{SS}	64.75		15.25	V
Shutdown Current	I_{DS} to I_{SS}	121	125	129	μA
Over Temperature				121	μA
TEMPERATURE RANGE					
Specification: P, U		-40		-85	°C
Thermal Resistance, θ_{JA}			100		°C/W
P			125		°C/W

ABSOLUTE MAXIMUM RATINGS

Total Supply Voltage Across Device (V_s) (max.)	11V
Internal Power Dissipation	See Thermal Considerations
Differential Input Voltage	V_d (total)
Conversion-Mode Input Voltage Range	$\pm 2V$
Storage Temperature Range: P, U	-40°C to $+125^\circ\text{C}$
Lead Temperature (soldering, 10s)	$+300^\circ\text{C}$
(soldering, SOIC 3s)	$+260^\circ\text{C}$
Junction Temperature (T_j)	$+175^\circ\text{C}$










PIN CONFIGURATION




NOTE: (1) Making use of all four power supply pins is highly recommended although not required. Using these four pins, instead of pins 4 and 7 only, will reduce the effective pin impedance and substantially improve distortion.

ch2 is
not connecte
to output
Power is ON OFF







The DC level at the input to the MVL407 on the 2735 is different for channel 1 on the 2735. The offset is approximately 20mV closer to GND than the other 15 channels. This was verified on three other unmodified 2735 cards.













Plots on p. 99 for modified 2735 show smaller Δ level difference than I recall seeing. All 3 unmodified cards were similar to levels on lower section of p. 99

Approximately a 15% reduction in pulse height from the addition of the MAX435.


unmodified	modified
2735	2735
2735	2735

modified 2735



unmodified 2735



6/15/96 Pressure Drop in 1/2" O.D. Polyflo Tubing




Black Ball at	Steel Ball at	DVM in mV	
Off	Off	-6	
15	1	9	.0072
34	16	43	.0344
56	29	104	.0832
82	42	197	.158
106	56	294	.235
132	69	390	.312
148	77	448	.358
	90.5	547	.438
	109.5	681	.545
	125	790	.632
	141	910	.728
Off	Off	-3	




Same as on p. 100 except use a
Dwyer 0 → 1 SCFH inexpensive
flowmeter.

6/19
JST
HCF

Pressure Drop in 1/2" O.D. Polyflo Tubing



Pressure Drop in 1/2" O.D. Polyflo Tubing




4.0 inches of pressure gives a 5 volt sensor output
0.1 SCFH = 47.2 sccm

$$\phi = \frac{\pi a^4 \Delta p}{8 \eta L}$$

η in Poise

Δp in dynes/cm²
(dynes/cm²) * 0.00401474 = in of H₂O

12/23/96 Propagation Velocity of IEEE 802.3 Cables





CH1 is at high impedance
CH3 is at 50Ω



Pocket pulser is plugged into BNC "T"
with LEMO to BNC & BNC "M" to BNC "M".

Comparing two 105' cables (carefully cut to length)
one of Belden 9907 and one of Alpha RG-58C/U

RG-58C/U



Belden 9907



$$105' = 32.004m$$

$$2.998E8 \text{ m/s}$$

$$V_{prop} = \frac{32.004}{\Delta t}$$




$$\frac{1.929}{2.998} = .643$$

$$\frac{2.353}{2.998} = .785$$



More Propagation Velocities of IEEE 802.3 Cables 12/25/96
 same setup as on p. 102

One cable is Comscope equivalent to Belden 9907.
 The other cable is an unknown manufacturer. It has
 a dark grey jacket.

Grey Jacketed IEEE 802.3




Comscope IEEE 802.3



$$\frac{2.283}{2.998} = .760$$

$$\frac{2.358}{2.998} = .787$$

12/25 Quick Look At Mlex Cable Assembly




AMP ribbon-ax assembly is one already in use in Hall A


Mlex sample is ~3' long with BNC on one end & 2 pin connector on the other end. 2 pin connector can be popped in & out of multi-contact housing. Good for trigger?

An additional piece of ~7' RG-58C/U was also used for the CUT. Two terminators I assembled were tried out. Terminators for miniature coax were the 50Ω 34 contact ones bought for the C&MAC discriminators.


~7' of
RG-58C/U
Terminated
in 49.9Ω
metal film
resistor




Mlex sample
cable term. in
50Ω





~7' of
RG-58C/U
terminated
in 51.1Ω
metal film
resistor



AMP ribbon-ax terminated
assembly in 50Ω




Further Molex Cable Investigations

12/28/96
JA


①

No cable attached. 28'6" section is open ended.




②

UG-914/U connector & 105' of cable barrel is marked 91836 UG-914/U




③

BNC "T" marked 91836 UG-274A/U & 105'




④

 $\times 105'$
Barrel marked M55339/16-00914
91836 759-1



unmarked commercial grade barrel
#105'


⑤



ATC insulated feedthru used on
patch panels #105'


marked ATC BNC - - - - -
can't read the numbers

⑥




BNC "T" marked 74868 U6-274 A/U
#105'

⑦




BNC "T" from ③ #105'
with commercial grade barrel ⑤ &
7' of RG-58 C/U unterminated
28' 6" 105'
T'

⑧




same as ⑧ except 7' section is terminated
with 51.1 Ω used on p. 104

⑨




cable disconnected as in ①


⑩




with Molex cable assembly attached and unterminated.



same as 11 except 50 Ω terminator in place












with AMP ribbonax assembly attached and unterminated.



same as 13 except 50 Ω terminator is in place

2/2/97 Meriter & Molex RG-178 Impedance Match












- ① "T" not connected to Ch3
② Ch3 @ 1MΩ & terminator on "T"

- ③ Ch3 @ 50Ω internal
④ Ch3 @ internal 50Ω feedthru removed
Will use 50Ω feedthru and internal terminator

- ⑤ longest Meriter cable is CUT

- ⑥ ⑦ & ⑧ are a bit confused.
My notes show 4 waveforms.
Apparently I didn't have one to disk. My notes show;
longest + one of the other two
longest + one more longest
CUT is one of Molex
one of Molex + one of Molex

Pocket pulser & 50 Ω feed thru replaced by Tektronix 109
PG2012.



① CUT is only 2 pin connector/jumper/splice (whatever)

② CUT is one of longer Meritec cable

③ CUT is one of longer Meritec + 1 of shorter Meritec

④ CUT is two of longer Meritec


⑤ CUT is one of Molex assemblies

⑥ CUT is two of Molex assemblies

⑦ & ⑧ are the same setup (cl hit Hardcopy twice)
CUT is 2 sections of AMP ribbon - ax. BNC ends are joined with a BNC barrel.
Used lines 2 & 16 of cable.






⑨ same as ⑧ except PG2012 replaced by pocket pulser & 50 Ω feed thru

Photocell - Laser Diode For Positioning



Laser printer gave some erratic results yesterday. I brought in the laser diode from p. 134 of Lab Techniques I. That gave stable results, but a much lower output signal.

The two upper pictures are of the laser pointer approximately centered between the two cells, ~26 feet away. The pointer was on for ~5 minutes before picture taken.



- ③ is APC driver & diode
~ 1/2" in front of left side
cell
- ④ is APC driver & diode
~ 1/2" in front of right
side cell
- ⑤ is APC driver & diode
~ centered between the
two cells

Radio Shack Photovoltaic Cell

2/8
JF

Photocell exposed to room light in Pm 122
provided about $\sim .33 \text{ mA}$ (measured with
Tenna 72-060 DMM. An inexpensive one)

$\sim 1.35 \text{ mA}$ of current when Radio Shack LX1000
pointer is shined from $11\frac{3}{4}''$ away. Made sure
dot fell between 2 of the metal stripes on the
front side.

$\sim 1.35 \text{ mA}$ from 2" away

$\sim .09 \text{ mA}$ with white $5\frac{1}{2}''$ deep, 3" ID
PVC pipe covering the photocell

2/15/97 Coherent Instruments Div. Laser Diode
 Part # 0220-999-00
 SYS, VLM2-1RL 1mW 670nm

@ ~5.2V supply, diode module draws 64mA. After current is increasing with time. Seems to be a temperature dependence. Warming my hand around the module makes the current increase faster.

Current is at 68.3mA
 Removing my hand and blowing on the module drops the current to ~67.8mA. Current increases again after I stop blowing.

Connect Radio Shack photovoltaic cell to Diode 8060A DMM.

Ambient light gives .344mA
 Laser @ 5V gives .800mA. Light strikes a metal stripe. After a few minutes it reads .806mA

Moving the spot around the maximum current is .818mA and minimum is .805mA

Current remains @ .806mA while voltage on module is increased to 9V




Visible Laser Module (VLM™): User Safety Precautions and Instructions

SAFETY PRECAUTIONS:

1. This product is classified as a Class II laser according to CDRH standards.
2. Since a laser beam can be damaging to the eyes, **DO NOT** look into the laser aperture when the laser is in operation. The emission indicator shows when laser is on.
3. Be aware that laser light can also be dangerous when reflected off a mirror-like surface.
4. For further safety information regarding lasers, refer to ANSI-Z136.1 STANDARD FOR THE SAFE USE OF LASERS, available from the Laser Institute of America, Tel (407) 380-1553.
5. CAUTION - Use of controls or adjustments or performance of procedures other than those specified herein may result in hazardous laser light exposure.

USER INSTRUCTIONS:

1. Electrical connection to the VLM™ is made through the red lead or the outside of the module (+) and the black lead or on end of the module (-). For safety reasons **DO NOT** permanently attach unit using alligator clips. The VLM™ has reverse polarity protection.
2. A voltage source of 5 to 10 VDC must be used. An adapter socket to supply power to the VLM™ is available. Contact your dealer for details.
3. CAUTION: The VLM™ contains a device sensitive to static and large transient spikes. If these spikes exceed 35 V, the VLM™ may be damaged.
4. **DO NOT** attempt to solder wire to the body or back of the VLM™. This will void the warranty and possibly damage the device.
5. POWER SUPPLIES: The VLM™ may be powered by either battery or line supplies. To avoid warranty questions: if line supply is used, ALS recommends that a pre-regulator, typically a 7805 or equivalent, be connected between the power supply and the VLM™ to filter out any transients. While recommended operating voltages for the VLM™ are between 5 VDC & 10 VDC, the VLM™ runs cooler and more efficiently at lower voltages.
6. SWITCHES: Any switch used in conjunction with a battery must have a low enough resistance to assure at least 5 VDC measured at the VLM™. If the battery is small, a momentary switch is best; however, with a 9 V battery a rocker or slide switch could be used.
7. Your VLM™ carries Applied Laser Systems' two-year limited warranty. You must fill out and return the Product Registration Card enclosed. The VLM™ contains no external controls, housing access or user serviceable items. If a failure occurs, **DO NOT** try to open or otherwise enter the VLM™; doing so will void the warranty. Simply call Applied Laser Systems at (503) 474-6560 and ask for a Return Authorization Number. Package the VLM™ and return it along with your Return Authorization Number to:



A solar cell is a silicon semiconductor device which converts light energy directly into electricity. A typical 7 x 4cm cell will produce 0.45 volt and up to 0.275 amp of usable current. The power generated is affected by the light intensity (circuit powered by cell), strength of sunlight and temperature.



Be extremely careful when soldering leads. Use only a very fine wire (#20 or thinner) and use a small soldering iron (less than 60 watts). Solar cells may be connected in series to produce more voltage and in parallel to produce more current.

Absolute Maximum Ratings
 Voltage (short circuit): 0.55V
 Current (short circuit): 0.3A
 Test conditions: Full sunlight at noon on a clear day at 75°C (78°F)



276-124

Assembled in U.S.A.
 With Domestic and Foreign Components.
 Custom Packaged in USA for Radio Shack
 A Division of Tandy Corp., Fort Worth, TX 76102



(continued on other side)

ALS
 APPLIED LASER SYSTEMS
 ATTN: Customer Service
 2160 NW Vine Street
 Grants Pass, OR 97526 USA
 Tel: (503) 474-6560
 FAX: (503) 476-5105

Quick Look at Sensitivity of Laser Positioning

3/23/97

Using laser and photocells from p. 12




Setup laser and photocells at opposite end of the light table in r.m. 122. 48" x 6" apart. Spot size on photocells is 3-4 mm in diameter.

The output of the photovoltaic cells is fed into the sample and hold circuit. This gives the difference of the two cells and background subtraction.

The output of the S+H circuit is monitored with an FET probe on CH1 of the TDS754 scope.

(well, not quite first)


First, the laser is tried without a light shield on the photocells. Erratic output is due to 120 Hz modulation of the room lights.




Same as above with a light shield in place. Light shield is a tube of black flocked paper from Edmund. The tube is placed immediately in front of the photocell. Black felt is used to cover the photocell stand.

Same as above with a 1.5V offset on CH1.


If this is due to some instability of the laser it should be less noticeable when the spot is centered between the two photocells. This was tried a little earlier. See next page. The erratic output seems to be from the switching of the laser. Perhaps it will improve with a real circuit board layout.




Light shield is in place. This is the noise with the spot on one side of the photocells. CH1 has a 5 offset applied.



This is the noise with the laser spot centered. Note that the amplitude is comparable to the upper picture.




Noise with the laser centered far above. CH2 is noise on 5V rail. CH2 has 5V offset applied to it.



Same as second picture above. This is in envelope mode to show the switching noise in the circuit CH2 only.


Photovoltaic cells are mounted on an angle on unistrut which can be moved by turning a 10-24 screw. Cells are moved $\perp$ to the laser beam. $\frac{1}{4}$ turn $\Rightarrow$ 42mils $\frac{1}{2}$ turn $\Rightarrow$ 21mils $\frac{1}{4}$ turn $\Rightarrow$ 10mils

Stepping the spot across the ^{gap (~25mil gap)} center of the two photocells. Using $\frac{1}{4}$ turns except for this one which is $\frac{1}{2}$ turn.



Traces stored in Refs to allow displaying multiple positions on one picture.








Moving from left side (looking from laser) to right side of beam.




(thickness)
 A piece of 5 mil mylar is placed
 in front of the laser. $\sim \perp$ to
 the beam.
 $\frac{1}{4}$ turn stepping over the center
 gap

Mylar is held by tape to
 be $\sim 45^\circ$ to the laser beam.
 $\frac{1}{4}$ turn stepping.

A piece of 2 mil thick kapton is
 placed in front of the laser.
 $\sim \perp$ to the laser beam.
 $\frac{1}{4}$ turn stepping.







Setup is moved to the aisle of the High Bay.
 This gives a separation of $\sim 111''$ for the laser and photovoltaic cells.
 The spot size is ~ 1.5 cm with annular rings at greater diameters.
 This is a tracing of approximate dimensions & edges of the rings. Spot shined on paper & then traced!



Note: The pictures below all have a 1.5V offset. I forgot to remove the offset after the pictures at the bottom of p. 113.


1 turn stepping. Except for one $\frac{1}{2}$ turn here, which was done by mistake



Vertical changed because I thought I was getting close to the gap.

2 mil thick bapton put in front of laser beam
 These two traces are of the same setup except the lower picture has bapton in front of the laser


Circuit for counting full revolutions




Discriminator outputs are normally LOW - go HIGH when turns

Handwritten notes: '2', '1', 'D-2' with arrows pointing to the circuit components.

+2.5V Source



IR LED Drive



Title Bogie Motor Rotary Encoder

Size	Number	Rev
C		1.0
Date	August 21, 1997	Drawn by Jack Segal
Filename	ROT_ENC.SCH	Sheet 1 of 1


Bogie Motor Shaft Encoders

8/2/97

The encoders are Renco model RH521-P3.

I have a good one and a "bad" one.

Looking from component side of PCB:





U_1, U_2 are MC33074 quad op amps

D_1, D_2 are LM319 dual comparators

LED is infrared - checked with infrared detector tab from Radio Shack

Receiver appears to be an array of photodiodes.  eight diodes or 2 arrays of 4

Encoder wheel has ~~two~~ three bands of significance. Outer band has a regular array of slits (radial) around it. Ratio of clear to obscured seems to be 1:1. Next ring inward is all metalized except for a small array of about 6 slits at one point of the circumference. The next ring inward is the opposite of the middle ring, open except for about 6 small stripes at the same point as the slits in the 2nd ring.



U_1, U_2 amps are $U_{1-1}, U_{1-2}, U_{1-3}$, etc. In same rotational sense as pin numbering.


$U_{1-2} + U_{2-2}$ are for the 4 PDs for the inner rings. They connect to the inner tab of PD package. Innermost tabs in the radial sense.

U_{1-3} connects to middle tab of PD package on its side of the package.


U_{1-4} connects to outer tab of PD package

All voltage measurements are made using an FET probe on the TDS 754A.

A $+2.5V$ reference is generated from $+5V$ by



Circuit for counting full revolutions. On PD array the inner 4 are used for this. There is a dog leg trace at the inner end of the PD package. The two inner most pads both go to the output tab away from the dogleg. The outer 2 pads go to tab by the dogleg.



When the marks on the inner two rings pass over PD
Output of U_{1-2} drops $\sim 180mV$

Output of U_{2-2} rises $\sim 180mV$

Output (mV below 2.5V) (when marks not over PD)

Which Chip
 U_{1-2} output
 U_{2-2} output

good encoder
 $\sim 100mV$
 $\sim 280mV$

bad encoder
 $\sim 400mV \leftarrow \text{eg. } \sim 2.1V$
 $\sim 1V$

D_{1-2} "+" input
 D_{1-2} "-" input



$\sim 50mV$
 $\sim 300mV$

$\sim 400mV \leftarrow \text{eg. } \sim 2.1V$
 $\sim 1V$

Output of "Bad" encoder D_{1-2}

Resistor values are from the bad encoder. Values which differ on the good encoder are shown in brackets [value]


encoder section seems to be insensitive to ambient light



Voltage on inputs of comparators (2.5V less indicated mV)

chip	good encoder	bad encoder	ie.
D ₁ -1 "-" input	~25mV	~25mV	2.5-75V
D ₁ -1 "+" input	1.0V _{pp} @ 2.5V	1.25V _{pp} @ (2.5V-350mV)	2-150V
D ₂ -2 "+"	~5V _{pp} @ (2.5-75V)	1.25V _{pp} @ (2.5-125mV)	

IR LED drive seems to be




← 1.15V drop on good unit (measured on good encoder. LED removed + drop checked with Fluke)

9/22


Verified D₁-2 does not change output state during a full rotation. On the bad encoder.

The extremes of the outputs of the amplifiers U₁-2 & U₂-2 are shown for the bad encoder. (actually, these are the ~~the~~ comparator inputs) (on D₁-2)




①

① pin 9
at a point of rotation away from the mark on the inner ring




②

② pin 9
when the mark gives ~ max deflection downward



③

③ pin 10
when the mark gives max deflection upward



④

④ pin 10
at a point of rotation away from the mark on the inner ring

8/24
JA

Using Fluke DMM;

	bad	good
across LED	1.357V	1.320


LED left leg	1.400	1.353
LED right leg	0.042	0.033
Diode (?) left	1.400	1.353
right	4.166	4.190
180Ω high	5.008	5.016
low	1.400	1.354
240Ω high	4.113 5.008	5.016
low	4.113	4.162
end of trace connected to diode right	4.113	4.162
~2.5V ref	2.442	2.439

These measurements seem to bear out the inferred circuit at the bottom of p. 119 of this volume.

Voltage drop across the "diode" is $\frac{4.190}{-1.353} = 2.837V$ on good encoder

Current through 240Ω is $\frac{2.854}{240} = 3.6mA$ on good encoder


Current through 180Ω is $\frac{3.662}{180} = 20mA$ on good encoder



Upper trace is U_1-4
Lower is U_1-3 } bad decoder

Outputs at the two extremes of value


2V offset both channels



Upper trace is U_1-4
Lower is U_1-3 } good decoder

Outputs at the two extremes of value


2.5V offset both channels



Upper trace is U_2-1
Lower is U_2-4 } bad decoder

Outputs at the two extremes of value


2.0V offset both channels



Upper trace is U_2-1
Lower trace is U_2-4 } good decoder

Outputs at the two extremes of value


2.5V offset both channels
Note: PD connection to U_2-1 lost during attempt to remove PD from board (prior attempt)



Upper trace is U_1-2
Lower is U_2-2 } good decoder


Outputs at the two extremes of value

2.5V offset both channels



Upper trace is U_1-2 output
Lower is D_1-2 "+" input
at the two extremes of value

Note the hysteresis on D_1-2 "+" input
(compare to U_1-2 output in both pictures)



U₁-4 output good encoder 2.5V-.14V to 2.5V-.26V $\Delta=120\text{mV}$
 bad encoder 2V-.1V to 2V-.22V $\Delta=120\text{mV}$

drop of 460mV for "baseline"
 bad has 348k for feedback
 good has 316k

$$348\text{k} \cdot 1.3\mu\text{A} = 464\text{mV}$$

↑
from rest one ↓

U₁-3 output good encoder 2.5V-.25V to 2.5V-.15V $\Delta=100\text{mV}$
 bad encoder 2V-.15V to 2V-.04V $\Delta=110\text{mV}$

drop of 400mV for "baseline"
 both good & bad have 300k for feedback
 $\Rightarrow 1.3\mu\text{A}$

U₂ A1 output 2.5V-.06V to 2V-.07V gives 370mV
 $1.3\mu\text{A} \cdot 330\text{k}$

U₂-1 doesn't count since PD connection is broken!!


U₂-4 output good encoder 2.5-.27 to 2.5-.15 $\Delta=120\text{mV}$
 bad encoder 2-.22 to 2-.08 $\Delta=140\text{mV}$

drop of 450mV for "baseline"
 $348\text{k} \cdot 1.3\mu\text{A} = 464\text{mV}$

8/31
PS

Diode Leakage Currents

Trying to measure leakage currents




Looking at output with no input on "-"
 0.0mV using Fluke DM73A
 1N914 diode to $V+ = 2.9V$ inserted at "-" input.
 Allowed to settle for 1 min $V_{out} = 29.4mV$
 30.3mV with fluorescent light on the diode
 With penlight I get $\sim 150mV - 28.9mV =$
 not real stable light off (before turned on)
 1N914 - unknown manuf. & date
 Motorola 1N5401 dated 8248

$V+$	V_{out}	V_{out}
2.9V	29.5mV	46mV
4.0	31.4	50
5.0	32	52
7.0	34	57
10.0	37	64
15.0	41	72
20.0	44	79
25.0	47	84
30.0	50	89

The 914 does not "see" the Fe^{55} source with
 $V+ = 2.5V$

1N5401 also does not "see" the source ($@ V+ = 30.0V$)
 Fe^{55} is listed as $500\mu Ci$

Diode Leakage Current




12/25 First Look at 931B PMT


Trying a transistorized base for a 931B.

Trying for a fast, high rate tube for background rates.

Base used is





Another base is constructed with $100 k\Omega$ between all stages. $0.01 \mu F$ from D₉ to GND, also.



output of 931B with NO scintillator on it.
Output of cosmic pulse or dark current pulse? ("noise")



Can't see Fe^{55} source with the tube. 500 μCi in '94

~6' of 50 Ω POMONA cable from base BNC to scope.
scope input set to $1 M\Omega$ BNC "T" with a
50 Ω terminator on it is used at scope.





a couple of "noise" pulses from
PMT with scintillator attached


Using Fe^{55} gives pulses similar to
these.




Larger pulses from PMT with
scint attached.
← No source
Probably cosmic



Typical pulses from
resistive base with PMT
with scint. attached




added another ~6' piece of POMONA cable
to the output




Removed extra ~6' POMONA cable.
Removed .01 μ F from D9 to GND, also.

10/26 Continuing 93/B Investigations
 JS Modified resistive base to bring out a signal from D9 and D8 as well as from the anode.



PMT HV set to -900V
 Fe^{55} source set on scint attached to PMT.




1.5ms RG-174 cables are unterminated

AVG set to 16

terminated D8 cable with 50 Ω BNC.
 D9 unterminated


AVG 16 traces




Both D8 & D9 cables are terminated in 50 Ω

AVG set to 16


D8 cable ~~short~~ terminated in 50 Ω
 D9 cable terminated in a shorting cap.
 AVG set to 16




~6' of POMONA cable added to each RG-174 cable.
 Connected to scope with BNC "T" & 50Ω terminator.
 typical pulses




scope set to AVG/16




shifted CH2 + CH3 to the left by ~1ns
 to correct for additional RG-174 as compared
 to anode cable length
 (same as above except for shifted)




reset horizontals




shifted CH2 + CH3 to the left by 7ns
 (same as above except for shifted)




typical pulse - CH2 + CH3 are still shifted
 by 7ns




typical pulse




50 Ω terminator removed from D9 cable



D9 BNC "T" removed from scope input



POMONA cable detached from RG-174 on D9




D9 RG-174 cable removed from D9
 .01 μ F capacitor attached to ground directly
 (50K also removed)

Base and Tube for Background Measurements

131

done at 10/27
written on 11/9/97



11/8

Setup for Measuring Charge on a Raindrop


This idea was from the ^{August} Sept. issue of Scientific American.

Measure the induced charge on a cylinder as the raindrop falls through the axis.

Two sheets of copper are wound on an aluminum tube. One on the inside, the other on the outside. Aluminum tube has ID of $2\frac{7}{8}$ "

The copper was held to its shape with tape while the seam was soldered. ^{OD of 3"} Not thus, have two copper tubes. One fits inside the other. The smaller diameter copper tube is also $\sim \frac{1}{2}$ " shorter than the other tube.


The larger diameter copper tube is used as a guard for the inner tube. Thus the guard extends $\sim \frac{1}{4}$ " above and below the ends of the smaller copper tube.




Outer tube has tape built up on its ID. This holds the inner copper tube in place by friction. The coax cable is attached at one end of the 2 tube assembly.

A LF356 and a CA3140 are compared. The CA3140 seems to oscillate. It quiets down if I hold my hand against the outer guard copper cylinder.


The safety gap of an "x-acto" knife is taped to the end of a small diameter brass tube. The cap is pushed against my jacket to build up a static charge and then poked into the tubes.




LF356 amp with a "small" charge on the plastic safety cap.





CA3140 amp with the same charge on the cap. "Same charge" in that the cap was not rubbed on the jacket. It was just lying around while the amps were swapped.



CA3140 amp after the cap was rubbed against the jacket again



LF356 amp. The cap was just lying around while the amps were swapped.



LF356 amp after the cap was rubbed against the jacket. Both pictures are of cap with the "same" charge.

So, how much charge does one raindrop carry? From Sci. Am. article the typical reading is $\sim 0.3 \mu\text{C}$. This is with a following stage with a gain of $1 + \frac{24k}{TR} = 2.5$
 $\Rightarrow 12 \text{ mV}$ for a typical raindrop







11/10 Charge on a Drop Tests

The setup used on p. 132 & 133 is tested with charged drops of water. The water is squeezed out of a squirt bottle onto a plastic bag. Then it is allowed to run off the bag and through the copper tubes. The amp used is a CA3140 with .01 μ F bypass from V^+ to V^- . It is stable in this configuration. It is NOT the same CA3140 used on p. 132.



The pulse height does bear some direct relation to the size of the drop.

Typical pulses out are shown.

The plastic bag was rubbed against miscellaneous objects to try to add charge to it.



Ken's Feedback Analysis (For rain monitor) 11/29/97 KN



Thevenin - equiv of feedback network

$$1 - B_1 = \frac{R_1}{R_1 + R_2 + R_3} = \frac{1}{307} = 3.3 \times 10^{-3}$$

$$1 - B_2 = \frac{R_1 + R_2}{R_1 + R_2 + R_3} = \frac{7}{307} = 2.4 \times 10^{-3}$$

$$i_s = i_D + i_C + i_R$$



$$i_D \frac{1}{j\omega C} = v_D = \frac{v_o}{A} \Rightarrow i_D = v_o j\omega \frac{C_D}{A}$$

$$(v_o + v_D - B_1 v_o) = i_R (R_F + R_1) \Rightarrow i_R = v_o \frac{1}{R_F} (1 - B_1 + \frac{1}{A})$$

$$(v_o + v_D - B_2 v_o) = i_C (\frac{1}{j\omega C_F} + B_2 R_2) \Rightarrow i_C = v_o j\omega C_F (1 - B_2 + \frac{1}{A})$$

$$i_s = v_o \left[\frac{1}{R_F} (1 - B_1) + j\omega C_F (1 - B_2) + \frac{1}{A} (j\omega (C_D + C_F) + \frac{1}{R_F}) \right]$$


$$\Rightarrow v_o = i_s \frac{R_F / (1 - B_1)}{1 + j\omega R_F C_F \left(\frac{1 - B_2}{1 - B_1} \right) + \frac{1}{A(1 - B_1)} (1 + j\omega (C_D + C_F) R_F)}$$



12/14/97 RG-58C/U, RG-58A/U and RG-59U Impedance Mismatch Demo I















Trying to get a visual demonstration of impedance mismatch problems with different cables.

Cables are
RG-58C/U
RG-58A/U
RG-59U



Note the fall time of ~ 20 ns.

Cable lengths measured by laying the cable on the floor of room 122 of FTEL and counting floor tiles, then cutting the cable to length. 6" $\pm$ 1/2" measured with a ruler. Cable lengths are before the connectors were attached.
i.e. cables cut to 3, 5 & 10 floor tiles length.
Also, 15' cables are 15 floor tiles length.

CUT
RG-58A/UCUT
IS
just
a BNC
barrel
connectorCUT
RG-59U6"
long1'
long3'
long5'
long10'
long10' of
RG-59UBarrel
connector
only

5/31/81 First Try at a resistive Base for 8575 PMT

Assembled a passive base for testing the 8575's.


Approximate the suggested divider "C" from the Burle catalog. Use $R = 240k$

$$1.6R = 330k$$


$$4R = 390k + 200k(\text{pot}) + 390k$$

The base displays ringing similar to the ringing of the 9313 base on p. 126 of this lab book. Except the ringing is more pronounced.

The ringing had a period of ~ 1.5 divisions







Thinking the ringing was due to some feedback loop involving the capacitors I re-did the divider.



The ringing is similar. I believe the frequency has changed. I seem to recall the ringing of the upper divider to have been ~ 1.5 divisions @ 1ns/div.

Cs^{137} source & a scrap piece of ~1cm thick scintillator are taped to the front of the tube. (cathode)

Typical pulses showing ringing




In InstaVu mode

Envelope mode
50 envelopes

This is about the full extent in time for the after pulsing in the PNT

6/1 Further Study of 8575 Resistive Base

Looking at the base on the lower half of p. 138




or in another way

dynode to
diode
capacitance

lead
inductance
in PNT

240k of divider

ignoring the 240k and lumping elements together



looking just at $\omega = 2\pi f$

resonance is $\omega_0 = \frac{1}{2\pi\sqrt{LC}}$

$$\omega^2 = \frac{1}{LC}$$

$$10\text{ nH} + 10\text{ pF} \Rightarrow 503\text{ MHz}$$

$$20\text{ nH} + 20\text{ pF} \Rightarrow 251\text{ MHz}$$

for these values and the critical damping point
for an RLC of $\frac{R^2}{4L^2} = \frac{1}{LC}$

$$R^2 = \frac{4L}{C}$$

$$R = 63\Omega$$

$R_{\text{crit.}} = 15\Omega$ for 250 MHz values

which gives a τ of $\frac{2L}{R} = 2.7\text{ ns}$

for 40 nH + 10 pF $\Rightarrow 251\text{ MHz}$

$$\text{and } R_{\text{crit.}} = 126.5\Omega$$

$$\Rightarrow \tau = .6\text{ ns}$$











I put 15 ohms in series with the dynodes.



-2400V

15 ohms
in series
with dynode
12







15 ohms in
series with
dynodes
12 & 11

-2400V






15 ohms in series with
dynodes 12, 11 & 10, 9 & 8
-2200V







same as above
except -2400V







1

c2


Same base as on 142.
New tube from Burle.
-1800V



2nd tube George
Lolor and Zips
removed from
the scintillators
due to low gain.
Same base as
above.
-2400V



envelope →
mode
5D envelopes



6/3

dynode?
as floating!


Borrowed an electronic capacitance meter from Hall B. With the leads attached it reads $\sim 82.4 \text{ pF} \sim 78 \text{ pF}$. Attaching the leads to the 1st + ~~2nd~~ 3rd dynode from the cathode gives a reading of $\sim 82.4 \text{ pF}$.

$\Rightarrow \sim 4.4 \text{ pF}$ for dynode to dynode

12 pF from DY1 to DY2. 6 pF for leads used.
same from DY2 to DY3.
same from DY1 to DY3.

ØØ1Ø4B34F5EF

S/N 6MD134F5EF



82.4











78.0

4.4 pF











$$L = \frac{1}{\omega^2 C}$$

$\cdot 3 \mu \text{H} / ??$

15 Ω in series with
last 5 dynodes
12, 11, 10, 9 & 8
001 μ F caps are
removed

















No 15 Ω resistor
No capacitors

















5 sec persistence

no 15 ohm
resistors
no capacitor

source about
1 inch away
from
scintillator
(lower
rate)






















Dynode 12 (last one) bypassed to gnd with .001 μ F



source against
scintillator

← → dynode 12 bypassed - source ~ 1 inch
way from scint. (lower rate)





*Py node 12 bypassed with
0.001 μ F
Source ~1" away from
scint. (lower rate.)*











Check of Wire Chamber for Photon Calorimeter 6/9/98

Looking at Bogdan W's wire chamber setup for the photon calorimeter on the floor.

-2510V (on Betan monitor output)
 Sr^{90} source ~1.5" from chamber
 2 FET probes on pins of T_{in}F
 "T" at input of 4448 module

200' of T_{in}F from 2735 to latch modules.


Typical ECL signals at input of 4448




Sr^{90} source held closer to the chamber.
 FET probe on the 2735 card.
 Amplifier output.

FET probe on amplifier output.
 Fe^{55} source taped to hole in center of cover over the chamber.


2510V




2300V



2400V




same
photo
(pushed
button
twice)




2400V


Blew fuse on -5.2V
 supply of card.
 replaced card.
 2400V




2550V



2550V



2600V



The threshold supply is set to 1.06V $\Rightarrow$ -9mV at input of comparator
 $\Rightarrow$ 42 $\rightarrow$ 46mV signal at comparator input
 FET probe was on top end of 220 Ω resistor to ground after LC combination out of amplifier

